

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	01240919	Call Order: 001	Proposal: E1V13	District:01
Counties:	HARDEE			
Road Name:	SR 66			
Limits:	06080000			
Project(s):	44893915201(*)	Federal Aid No: N/A		
Total Roadway Length:	7.730 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	09/19/24	
Total Proposal Length:	7.730 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$6,567,457.83			

Please read the full advertisement

Description:

The improvements under this Contract consist of milling and resurfacing and pavement markings on SR 66 from West of Sweetwater Road to Highlands County line in Hardee County.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E1V13**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44893915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44893915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,200.000
	0102- 60-	WORK ZONE SIGN	ED	8,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	21,000.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	328.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	300.000
	0104- 10- 3	SEDIMENT BARRIER	LF	83,116.000
	0107- 1-	LITTER REMOVAL	AC	403.100
	0107- 2-	MOWING	AC	356.300
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	109,661.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	42,917.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	9,047.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	12,587.800
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	24,048.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,147.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	15.465
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	127.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.147
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	7.475
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44893915201)	LS	1.000
<b>Section 0002 Signing</b>				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,143.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44893915201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	104.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.022
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	15.465
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.116
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	7.475