

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01250821	Call Order: 002	Proposal: E1X69	District:01
Counties:	POLK			
Road Name:	SR 600			
Limits:	16020000			
Project(s):	45087415201(*)	Federal Aid No:	N/A	
Total Roadway Length:	11.460 Miles	Contract Days:	180	
Total Bridge Length:	0.000 Miles	Letting Date:	08/21/25	
Total Proposal Length:	11.460 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days(Acqui. Time)	
Proposal Budget Estimate:	\$10,664,611.00			

Please read the full advertisement

Description:

The improvements under this contract consist of Milling and Resurfacing, Pavement Markings, loop assemblies and Curb Ramp Replacement on State Road 600 (US 92 / US 17) from West of Ramona Ave to 3rd Street in Polk County.

Call Order: 002 Proposal: E1X69

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45087415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45087415201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45087415201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,070.000
	0102- 60-	WORK ZONE SIGN	ED	27,232.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	44,460.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	60,943.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	289.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	208.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,992.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	180.000
	0102-115-	TYPE III BARRICADE	ED	408.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	360.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	360.000
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	173.000
	0104- 10- 3	SEDIMENT BARRIER	LF	406.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	14.000
	0107- 1-	LITTER REMOVAL	AC	572.400
	0107- 2-	MOWING	AC	538.800
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (45087415201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45087415201)	LS	1.000

Call Order: 002 Proposal: E1X69

ALT	Item	Description	Unit	Quantity
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	148.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	164,293.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	72,372.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,253.300
	0334- 1- 57	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, HIGH POLYMER	TN	13,554.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,843.100
	0337- 7- 93	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, HIGH POLYMER	TN	15,429.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	207.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	115.000
	0527- 2-	DETECTABLE WARNINGS	SF	86.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	26,210.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,506.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	12.070
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.105
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,031.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	1,347.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	792.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	11.745
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.279
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	68.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	9.680
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	308.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	2.219
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45087415201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	13.025
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,506.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	995.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45087415201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.105
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,031.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,347.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	792.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.049

Call Order: 002 Proposal: E1X69

ALT	Item	Description	Unit	Quantity
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	68.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	308.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	2.219
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	12.070
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	11.745
	0711- 16-171	THERMOPLASTIC, STANDARD OTHER SURFACES, WHITE, 6", 6-10 DOTTED MANAGED LANE MARKING	GM	0.230
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	9.680
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	60.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	180.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	4.000
	0660- 2-105	LOOP ASSEMBLY, F&I, TYPE E	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000