

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01250821	Call Order: 003	Proposal: E1X70	District:01
Counties:	POLK			
Road Name:	SR 37			
Limits:	16250000			
Project(s):	45089015201(*)	Federal Aid No:	N/A	
Total Roadway Length:	4.192 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	08/21/25	
Total Proposal Length:	4.192 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days (Aqui Time)	

Proposal Budget Estimate: \$7,515,025.61

Please read the full advertisement

Description:

The improvements under this contract consists of milling and resurfacing, pavement markings, and signalization on SR 37 from north of Virginia Street to south of Schoolhouse Road in Polk County.

Call Order: 003 Proposal: E1X70

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45089015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45089015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	116.000
	0102- 60-	WORK ZONE SIGN	ED	14,400.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	15,274.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	150.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	490.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	750.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	750.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	212.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	212.000
	0104- 10- 3	SEDIMENT BARRIER	LF	9,258.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	28.000
	0107- 1-	LITTER REMOVAL	AC	472.220
	0107- 2-	MOWING	AC	431.260
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	207,876.000
	0337- 7- 95	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, HIGH POLYMER	TN	22,866.500
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	17,532.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45089015201)	LS	1.000

Call Order: 003 Proposal: E1X70

ALT	Item	Description	Unit	Quantity
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	6.425
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	12.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	122.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,410.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	683.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	904.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45089015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	4,881.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	3,429.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	844.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.469
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	16.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	430.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	15.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2,259.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.210
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	3,412.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	12.871
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.674
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	7.953
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	7.767
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.161
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	188.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	22.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	22.000