

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

| | | | | |
|---------------------------|---|----------------------------|---------------------|-------------|
| Letting: | 01250220 | Call Order: 001 | Proposal: E1W90 | District:01 |
| Counties: | COLLIER | | | |
| Road Name: | COLLIER COUNTY - BRIDGE-REPAIR/REHABILITATION | | | |
| Limits: | 03010000 | | | |
| Project(s): | 43504315201(*) | Federal Aid No: N/A | | |
| Total Roadway Length: | 0.048 Miles | Contract Days: | 240 | |
| Total Bridge Length: | 0.048 Miles | Letting Date: | 02/20/25 | |
| Total Proposal Length: | 0.096 Miles | Contract Execution Days: | 10 | |
| | | Special Start Date: | N/A | |
| | | Aquis/Flexible Start Time: | 60 Days (Aqui Time) | |
| Proposal Budget Estimate: | \$2,974,133.41 | | | |

Please read the full advertisement

Description:

The improvements under this Contract consist of spall repair, deck joint repair, pile jacket installation, crutch bent and riprap scour protection countermeasure at Bridge Nos. 030039, 030068 and 030071 in Collier County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 001 Proposal: E1W90

| ALT | Item | Description | Unit | Quantity |
|--------------------------------|--------------|---|------|------------|
| Section 0001 Structures | | | | |
| | 0104- 11- | FLOATING TURBIDITY BARRIER | LF | 3,368.000 |
| | 0108- 1- | MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43504315201) | LS | 1.000 |
| | 0110- 1- 1 | CLEARING & GRUBBING (43504315201 BR# 030039) | LS | 1.000 |
| | 0110- 1- 1 | CLEARING & GRUBBING (43504315201 BR# 030068) | LS | 1.000 |
| | 0110- 1- 1 | CLEARING & GRUBBING (43504315201 BR# 030071) | LS | 1.000 |
| | 0120- 5- | CHANNEL EXCAVATION | CY | 1,312.800 |
| | 0400- 4- 5 | CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE | CY | 202.800 |
| | 0401- 70- 4 | RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT | CF | 34.900 |
| | 0415- 1- 5 | REINFORCING STEEL- BRIDGE SUBSTRUCTURE | LB | 58,200.000 |
| | 0455- 15- 13 | PREFORMED PILE HOLES, 22" TO 26" DRILL/PUNCH SIZE | LF | 332.000 |
| | 0455- 15- 26 | PREFORMED PILE HOLES CASING, 36" TO 43" DRILL/PUNCH SIZE | LF | 208.000 |
| | 0455- 20- 1 | PILE INSPECTION, DRIVEN PILE | EA | 16.000 |
| | 0455- 34- 5 | PRESTRESSED CONCRETE PILING, 24" SQ | LF | 912.000 |
| | 0455-115- | PILE REDRIVE | EA | 4.000 |
| | 0455-137- | LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS | EA | 16.000 |
| | 0455-137- 2 | LOAD TEST (DYNAMIC), VERIFICATION TEST | EA | 8.000 |
| | 0457- 1- 11 | STANDARD INTEGRAL PILE JACKET, NON-STRUCTURAL, UP TO 16" | LF | 170.000 |
| | 0458- 1- 21 | BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD | LF | 334.000 |
| | 0458- 2- | POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT | CF | 209.000 |
| | 0530- 3- 4 | RIPRAP, RUBBLE, F&I, DITCH LINING | TN | 1,079.900 |
| | 0530- 74- | BEDDING STONE | TN | 639.400 |
| Section 0002 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (43504315201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (43504315201) | LS | 1.000 |
| | 0102- 14- | TRAFFIC CONTROL OFFICER | HR | 1,100.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 5,160.000 |
| | 0102- 71- 15 | TEMPORARY BARRIER, F&I, ANCHORED | LF | 125.000 |
| | 0102- 71- 16 | TEMPORARY BARRIER, F&I, FREE STANDING | LF | 975.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 9,672.000 |
| | 0102- 89- 1 | TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION | LO | 2.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 1,158.000 |
| | 0102-120- | TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE, TWO-WAY ROADWAYS | ED | 80.000 |
| | 0102-909- | TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS | DA | 40.000 |
| | 0102-913- 23 | REMOVABLE TAPE, WHITE, 24" STOP BAR | LF | 22.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43504315201) | LS | 1.000 |