

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	01250116	Call Order: 001	Proposal: E1W90	District:01
Counties:	COLLIER			
Road Name:	COLLIER COUNTY - BRIDGE-REPAIR/REHABILITATION			
Limits:	03010000			
Project(s):	43504315201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.048 Miles	Contract Days:	240	
Total Bridge Length:	0.048 Miles	Letting Date:	01/16/25	
Total Proposal Length:	0.096 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	
Proposal Budget Estimate:	\$2,974,133.42			

Please read the full advertisement

Description:

The improvements under this Contract consist of spall repair, deck joint repair, pile jacket installation, crutch bent and riprap scour protection countermeasure at Bridge Nos. 030039, 030068 and 030071 in Collier County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 001 Proposal: E1W90

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	3,368.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43504315201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43504315201 BR# 030039)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43504315201 BR# 030068)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43504315201 BR# 030071)	LS	1.000
	0120- 5-	CHANNEL EXCAVATION	CY	1,312.800
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	202.800
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	34.900
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	58,200.000
	0455- 15- 13	PREFORMED PILE HOLES, 22" TO 26" DRILL/PUNCH SIZE	LF	332.000
	0455- 15- 26	PREFORMED PILE HOLES CASING, 36" TO 43" DRILL/PUNCH SIZE	LF	208.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	16.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	912.000
	0455-115-	PILE REDRIVE	EA	4.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	16.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	8.000
	0457- 1- 11	STANDARD INTEGRAL PILE JACKET, NON-STRUCTURAL, UP TO 16"	LF	170.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	334.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	209.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	1,079.900
	0530- 74-	BEDDING STONE	TN	639.400
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43504315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43504315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,100.000
	0102- 60-	WORK ZONE SIGN	ED	5,160.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	125.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	975.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,672.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,158.000
	0102-120-	TEMPORARY TRAFFIC SIGNALS FOR LANE CLOSURES ON TWO-LANE, TWO-WAY ROADWAYS	ED	80.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	40.000
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	22.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43504315201)	LS	1.000