

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01251016	Call Order: 001	Proposal: E1W11	District:01
Counties:	POLK			
Road Name:	SR 17			
Limits:	16090000			
Project(s):	45088215201(*)	Federal Aid No: N/A		
Total Roadway Length:	2.246 Miles	Contract Days:	80	
Total Bridge Length:	0.000 Miles	Letting Date:	10/16/25	
Total Proposal Length:	2.246 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days	
Proposal Budget Estimate:	\$1,878,077.34			

Please read the full advertisement

Description:

The improvements under this project consist of milling and resurfacing and pavement markings on SR 17 from North of Waverly Road (CR 540) to South of Lake Trask Road in Polk County.

Call Order: 001 Proposal: E1W11

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45088215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45088215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	800.000
	0102- 60-	WORK ZONE SIGN	ED	3,680.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	160.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	188.000
	0102-115-	TYPE III BARRICADE	ED	400.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	80.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,380.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	7.000
	0107- 1-	LITTER REMOVAL	AC	54.510
	0107- 2-	MOWING	AC	50.880
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	11,716.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	28,251.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,942.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	3,297.300
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,029.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	553.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.101
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	37.000

Call Order: 001 Proposal: E1W11

ALT	Item	Description	Unit	Quantity
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	28.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	8.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.472
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	180.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.395
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.025
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45088215201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	5.794
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	553.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45088215201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	37.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	28.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	8.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	180.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.025
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.101
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.472
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.395