

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01251016	Call Order: 006	Proposal: E1Y14-R0	District:01
Counties:	DESOTO, GLADES, HARDEE, HENDRY, HIGHLANDS			
Road Name:	Pipe Lining, Repair, Desilting and Video Inspection			
Limits:	Midpoint			
Project(s):	43792917290(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	10/16/25	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$250,000.00

Please read the full advertisement

Description:

The work under this Contract consists of Pipe Lining, Repair, Desilting and Video Inspection.

Call Order: 006 Proposal: E1Y14-R0

ALT	Item	Description	Unit	Quantity
Section 0001 PRESSURE GROUTING (CF)				
	0173- 77- 3	SUBSURFACE PRESSURE GROUTING, CEMENT SLURRY	CY	9.000
	0425- 74- 1	MANHOLES & INLETS CLEANING & SEALING, <10'	EA	7.000
	0906-173-200	TWO COMPONENT POLYURETHANE INJECTION	LB	5,000.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	9.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	1,000.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	1,125.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	515.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	2,135.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	4,800.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	6.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	5.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	10.000
	E431- 1- 31	PIPE LINER, SLIP LINER, 0-24"	LF	10.000
	E431- 1- 32	PIPE LINER, SLIP LINER, 25-36"	LF	10.000
	E431- 1- 33	PIPE LINER, SLIP LINER, 37-48"	LF	10.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	18,300.000