

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

|                           |                 |                            |                 |             |
|---------------------------|-----------------|----------------------------|-----------------|-------------|
| Letting:                  | 01250918        | Call Order: 001            | Proposal: E1X73 | District:01 |
| Counties:                 | POLK            |                            |                 |             |
| Road Name:                | SR 555          |                            |                 |             |
| Limits:                   | 16030000        |                            |                 |             |
| Project(s):               | 44742815201(*)  | Federal Aid No:            | N/A             |             |
| Total Roadway Length:     | 9.334 Miles     | Contract Days:             | 260             |             |
| Total Bridge Length:      | 0.000 Miles     | Letting Date:              | 09/18/25        |             |
| Total Proposal Length:    | 9.334 Miles     | Contract Execution Days:   | 10              |             |
|                           |                 | Special Start Date:        | N/A             |             |
|                           |                 | Aquis/Flexible Start Time: | 15 Days         |             |
| Proposal Budget Estimate: | \$10,438,215.27 |                            |                 |             |

Please read the full advertisement

**Description:**

The improvements under this project consist of milling and resurfacing, sidewalk, curb and gutter, loops and pavement markings on SR 555 (US 17) from N of Transport Rd to Avenue G SW in Polk County.

**Call Order: 001 Proposal: E1X73**

| ALT                         | Item         | Description                                                                     | Unit | Quantity   |
|-----------------------------|--------------|---------------------------------------------------------------------------------|------|------------|
| <b>Section 0001 Roadway</b> |              |                                                                                 |      |            |
|                             | 0101- 1-     | MOBILIZATION (44742815201)                                                      | LS   | 1.000      |
|                             | 0102- 1-     | MAINTENANCE OF TRAFFIC (44742815201)                                            | LS   | 1.000      |
|                             | 0102- 60-    | WORK ZONE SIGN                                                                  | ED   | 53,040.000 |
|                             | 0102- 74- 1  | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD                          | ED   | 46,800.000 |
|                             | 0102- 74- 8  | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)          | FD   | 46,800.000 |
|                             | 0102- 76-    | ARROW BOARD / ADVANCE WARNING ARROW PANEL                                       | ED   | 520.000    |
|                             | 0102- 99-    | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY                                     | ED   | 548.000    |
|                             | 0102-104-    | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION                           | ED   | 2,340.000  |
|                             | 0102-107- 1  | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION                       | ED   | 2,340.000  |
|                             | 0104- 10- 3  | SEDIMENT BARRIER                                                                | LF   | 789.000    |
|                             | 0104- 18-    | INLET PROTECTION SYSTEM                                                         | EA   | 188.000    |
|                             | 0107- 1-     | LITTER REMOVAL                                                                  | AC   | 407.390    |
|                             | 0107- 2-     | MOWING                                                                          | AC   | 340.470    |
|                             | 0108- 1-     | MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44742815201) | LS   | 1.000      |
|                             | 0110- 1- 1   | CLEARING & GRUBBING (44742815201)                                               | LS   | 1.000      |
|                             | 0110- 4- 10  | REMOVAL OF EXISTING CONCRETE                                                    | SY   | 380.000    |
|                             | 0120- 1-     | REGULAR EXCAVATION                                                              | CY   | 42.000     |
|                             | 0120- 6-     | EMBANKMENT                                                                      | CY   | 42.000     |
|                             | 0327- 70- 4  | MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH                                 | SY   | 76,133.000 |
|                             | 0327- 70- 6  | MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH                             | SY   | 27,626.000 |
|                             | 0327- 70- 7  | MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH                                 | SY   | 68,490.000 |
|                             | 0327- 70- 11 | MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH                             | SY   | 33,653.000 |
|                             | 0327- 70- 20 | MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH                             | SY   | 18,198.000 |

**Call Order: 001 Proposal: E1X73**

| ALT                         | Item         | Description                                                                                 | Unit | Quantity   |
|-----------------------------|--------------|---------------------------------------------------------------------------------------------|------|------------|
|                             | 0334- 1- 13  | SUPERPAVE ASPHALTIC CONC, TRAFFIC C                                                         | TN   | 15,675.100 |
|                             | 0334- 1- 55  | SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22                                            | TN   | 6,047.000  |
|                             | 0337- 7- 25  | ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22                                   | TN   | 2,080.500  |
|                             | 0337- 7- 83  | ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22                              | TN   | 13,832.700 |
|                             | 0520- 1- 10  | CONCRETE CURB & GUTTER, TYPE F                                                              | LF   | 400.000    |
|                             | 0520- 2- 4   | CONCRETE CURB, TYPE D                                                                       | LF   | 45.000     |
|                             | 0522- 1-     | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK                                                   | SY   | 97.000     |
|                             | 0522- 2-     | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK                                                   | SY   | 168.000    |
|                             | 0527- 2-     | DETECTABLE WARNINGS                                                                         | SF   | 303.000    |
|                             | 0570- 1- 2   | PERFORMANCE TURF, SOD                                                                       | SY   | 13,465.000 |
|                             | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                                              | EA   | 4,048.000  |
|                             | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"                                       | GM   | 10.561     |
|                             | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"      | GM   | 0.406      |
|                             | 0710- 11-123 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"         | LF   | 8,039.000  |
|                             | 0710- 11-124 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"              | LF   | 1,191.000  |
|                             | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"           | LF   | 5,132.000  |
|                             | 0710- 11-131 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE                | GM   | 14.609     |
|                             | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM   | 1.277      |
|                             | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS                                          | EA   | 242.000    |
|                             | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"                                      | GM   | 9.045      |
|                             | 0710- 11-224 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"             | LF   | 850.000    |
|                             | 0710- 11-231 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"                                       | GM   | 1.195      |
|                             | 0710- 11-241 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6" | GM   | 0.693      |
|                             | 0999- 25-    | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44742815201)                                        | LS   | 1.000      |
| <b>Section 0002 Signing</b> |              |                                                                                             |      |            |
|                             | 0546- 72- 3  | GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL                                                      | GM   | 3.323      |
|                             | 0704- 1- 4   | TUBULAR MARKER, 36" YELLOW POST                                                             | EA   | 8.000      |
|                             | 0706- 1- 3   | RAISED PAVEMENT MARKER, TYPE B                                                              | EA   | 4,020.000  |
|                             | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM   | 0.079      |
|                             | 0710- 12-290 | PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE                               | SF   | 187.000    |
|                             | 0710- 90-    | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44742815201)                                      | LS   | 1.000      |
|                             | 0711- 11-102 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND                  | GM   | 0.237      |
|                             | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT                     | LF   | 3,980.000  |
|                             | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS                       | LF   | 993.000    |

**Call Order: 001 Proposal: E1X73**

| ALT                               | Item         | Description                                                                                       | Unit | Quantity  |
|-----------------------------------|--------------|---------------------------------------------------------------------------------------------------|------|-----------|
|                                   | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK                            | LF   | 1,507.000 |
|                                   | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"                      | GM   | 1.280     |
|                                   | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL                                                 | EA   | 6.000     |
|                                   | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW                                                             | EA   | 238.000   |
|                                   | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON                               | LF   | 842.000   |
|                                   | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"            | GM   | 0.638     |
|                                   | 0711- 14-123 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK                                         | LF   | 3,703.000 |
|                                   | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK                                         | LF   | 3,511.000 |
|                                   | 0711- 15-101 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"                             | GM   | 10.225    |
|                                   | 0711- 15-102 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"                            | GM   | 0.149     |
|                                   | 0711- 15-131 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP | GM   | 14.609    |
|                                   | 0711- 15-201 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"                           | GM   | 9.045     |
|                                   | 0711- 15-231 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"                            | GM   | 1.195     |
| <b>Section 0003 Signalization</b> |              |                                                                                                   |      |           |
|                                   | 0660- 2-102  | LOOP ASSEMBLY, F&I, TYPE B                                                                        | AS   | 36.000    |
|                                   | 0660- 2-106  | LOOP ASSEMBLY, F&I, TYPE F                                                                        | AS   | 42.000    |