

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	01250918	Call Order: 004	Proposal: E1X76	District:01
Counties:	HENDRY			
Road Name:	SR 29			
Limits:	07060000			
Project(s):	45340115201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.520 Miles	Contract Days:	115	
Total Bridge Length:	0.000 Miles	Letting Date:	09/18/25	
Total Proposal Length:	0.520 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Aqui Time)	

Proposal Budget Estimate: \$921,522.31

Please read the full advertisement

Description:

The improvements under this project consist of drainage improvements, ditch reconstruction, pavement reconstruction and other incidental construction on State Road 29 from Oklahoma Ave to Park Ave in Hendry County.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 004 Proposal: E1X76

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45340115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45340115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,408.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	1,232.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	564.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	308.000
	0102-115-	TYPE III BARRICADE	ED	154.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,751.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	35.000
	0107- 1-	LITTER REMOVAL	AC	6.950
	0107- 2-	MOWING	AC	6.950
	0110- 1- 1	CLEARING & GRUBBING (45340115201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	53.000
	0120- 1-	REGULAR EXCAVATION	CY	1,726.700
	0120- 6-	EMBANKMENT	CY	105.200
	0160- 4-	TYPE B STABILIZATION	SY	257.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	204.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	302.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	41.700
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	21.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	188.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	5.000
	0430-548-130	STRAIGHT CONCRETE ENDWALLS, 48", SINGLE, 45 DEGREES, ROUND	EA	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-982-141	MITERED END SECTION, OPTIONAL ROUND, 48" CD	EA	5.000
	0430-982-142	MITERED END SECTION, OPTIONAL ROUND, 54" CD	EA	1.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	54.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	520.000
	0527- 2-	DETECTABLE WARNINGS	SF	43.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,305.000
	0571- 1- 12	PLASTIC EROSION MAT, TRM, TYPE 2	SY	1,804.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45340115201)	LS	1.000