

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01260115	Call Order: 001	Proposal: E1W96	District:01
Counties:	POLK			
Road Name:	FORT FRASER TRAIL OVER SR 60			
Limits:	Midpoint			
Project(s):	44027215201(*)	Federal Aid No:	N/A	
Project(s):	44027215202	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	375	
Total Bridge Length:	0.171 Miles	Letting Date:	01/15/26	
Total Proposal Length:	0.171 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days(Acqui Time)	

Proposal Budget Estimate: \$9,844,952.93

Please read the full advertisement

Description:

The Improvements under this Contract consist of construction of pedestrian bridge, milling and resurfacing, drainage, sidewalk, fencing, lighting, and signing and marking at Fort Fraser Trail over SR 60 in Polk County.

Mandatory Pre-Bid - Tuesday, November 18, 2025 @ 11:00 A.M.

Please join the meeting from your computer, tablet or smartphone.

<https://meet.goto.com/614374821>

You can also dial in using your phone.
 (For supported devices, tap a one-touch number below to join instantly.)

United States (Toll Free): 1 877 309 2073
 - One-touch: tel:+18773092073,,614374821#

United States: +1 (571) 317-3129
 - One-touch: tel:+15713173129,,614374821#

Access Code: 614-374-821

Join from a video-conferencing room or system.
 Dial in or type: 67.217.95.2 or inroomlink.goto.com
 Meeting ID: 614 374 821
 Or dial directly: 614374821@67.217.95.2 or 67.217.95.2##614374821

Call Order: 001 Proposal: E1W96

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	50.200
	0400- 2- 4	CONC CLASS II, BRIDGE SUPERSTRUCTURE	CY	29.200
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	46.100
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	474.100
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	176.800
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	91.600
	0400-147-	COMPOSITE NEOPRENE PADS	CF	12.800
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	119,908.000

Call Order: 001 Proposal: E1W96

ALT	Item	Description	Unit	Quantity
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	64,633.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	36,832.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	9,616.000
	0450- 2- 36	PREST BEAMS: FLORIDA-I BEAM 36"	LF	1,802.000
	0455- 15- 13	PREFORMED PILE HOLES, 22" TO 26" DRILL/PUNCH SIZE	LF	372.000
	0455- 15- 15	PREFORMED PILE HOLES, 30" TO 34" DRILL/PUNCH SIZE	LF	228.000
	0455- 15- 23	PREFORMED PILE HOLES CASING, 22" TO 26" DRILL/PUNCH SIZE	LF	372.000
	0455- 15- 25	PREFORMED PILE HOLES CASING, 30" TO 34" DRILL/PUNCH SIZE	LF	228.000
	0455- 15- 33	PREFORMED PILE HOLES GROUTING, 22" TO 26" DRILL/PUNCH SIZE	LF	372.000
	0455- 15- 35	PREFORMED PILE HOLES GROUTING, 30" TO 34" DRILL/PUNCH SIZE	LF	228.000
	0455- 20- 1	PILE INSPECTION, DRIVEN PILE	EA	38.000
	0455- 35- 21	STEEL PILING, 20" DIA. PIPE	LF	1,855.000
	0455-115-	PILE REDRIVE	EA	8.000
	0455-133- 2	SHEET PILING STEEL, TEMPORARY-CRITICAL	SF	1,898.000
	0455-137-	LOAD TEST (DYNAMIC), DATA COLLECTION AND ANALYSIS	EA	46.000
	0455-137- 2	LOAD TEST (DYNAMIC), VERIFICATION TEST	EA	10.000
	0455-144- 21	TEST PILES - STEEL, 20" DIA PIPE	LF	490.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	184.000
	0459- 71-	PILES, POLYETHYLENE SHEETING	SY	174.000
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	14,810.000
	0563- 4-	ANTI-GRAFFITI COATING, NON-SACRIFICIAL	SF	14,810.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44027215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44027215201)	LS	1.000
	0102- 5-	PEDESTRIAN ESCORT/FLAGGER	HR	216.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	144.000
	0102- 60-	WORK ZONE SIGN	ED	12,804.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	895.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,010.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	114,900.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	402.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	456.000
	0102-112-	EXISTING ITS MAINTENANCE	DA	375.000
	0102-115-	TYPE III BARRICADE	ED	3,542.000
	0104- 10- 3	SEDIMENT BARRIER	LF	4,407.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	3.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	16.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44027215201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (44027215201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44027215201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	125.000
	0120- 1-	REGULAR EXCAVATION	CY	9,246.000

Call Order: 001 Proposal: E1W96

ALT	Item	Description	Unit	Quantity
	0120- 6-	EMBANKMENT	CY	5,500.000
	0160- 4-	TYPE B STABILIZATION	SY	4,922.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	3,794.000
	0285-713-	OPTIONAL BASE, BASE GROUP 13	SY	19.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	2,008.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	295.200
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	2.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	165.600
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	1.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	2.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	2.000
	0425- 2- 41	MANHOLES, P-7, <10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	2.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	582.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	7.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	781.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY,42" TYPE 1	LF	2,697.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	611.000
	0521- 1- 14	MEDIAN CONCRETE BARRIER, VARIABLE SECTION WIDTH FOR SIGN OR PIER SHIELDING	LF	108.000
	0521- 6- 11	CONCRETE PARAPET, PEDESTRIAN/BICYCLE, 27" HEIGHT	LF	424.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	291.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,512.000
	0524- 1- 19	CONCRETE DITCH PAVT, 3", REINFORCED	SY	1.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	13.000
	0544- 3- 2	CRASH CUSHION, TL-3, WIDE	EA	2.000
	0550- 10-230	FENCING, TYPE B, 6.1-7.0', STANDARD	LF	410.000
	0550- 10-354	FENCING, TYPE R, 8.1-10.0', WITH PARTIAL ENCLOSURE, TYPE R ONLY	LF	424.000
	0550- 10-418	FENCING, WOOD FENCE, 0.0-5.0', RESET EXISTING	LF	550.000
	0550- 60-237	FENCE GATE, TYPE B, SLIDING/CANTILEVER, GREATER THAN 30' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	15,834.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	55.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.071
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	18.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.247
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.356
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.011
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	5.000
	0914-550- 3	FENCING- PEDESTRIAN BARRIER P3- 4' ROPE FENCE	LF	211.000

Call Order: 001 Proposal: E1W96

ALT	Item	Description	Unit	Quantity
Section 0003 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	5.000
	0700- 1-311	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	19.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	55.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	5.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44027215201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	18.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.011
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.071
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.247
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.278
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	184.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	62.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	300.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	7.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,566.000
Section 0005 Architectural				
	0751- 11-100	ARCHITECTURAL- SPECIAL, FURNISH AND INSTALL	EA	2.000