

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01260716	Call Order:	002	Proposal:	E1W98	District:	01
Counties:	POLK						
Road Name:	SR 17						
Limits:	16090000						
Project(s):	45088315201(*)	Federal Aid No:	N/A				
Total Roadway Length:	6.320 Miles	Contract Days:	125				
Total Bridge Length:	0.000 Miles	Letting Date:	07/16/26				
Total Proposal Length:	6.320 Miles	Contract Execution Days:	10				
		Special Start Date:	N/A				
		Aquis/Flexible Start Time:	15 Days				

Proposal Budget Estimate: \$4,364,273.54

Please read the full advertisement

Description:

The improvements under this contract consist of milling and resurfacing, and pavement markings on SR 17 from North of Old Scenic Highway to Lake Marion Road (SR 544) in Polk County.

Call Order: 002 Proposal: E1W98

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45088315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45088315201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	190.000
	0102- 60-	WORK ZONE SIGN	ED	2,750.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	13,750.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	278.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	500.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	500.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	120.000
	0104- 10- 3	SEDIMENT BARRIER	LF	13,391.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	56.000
	0107- 1-	LITTER REMOVAL	AC	122.190
	0107- 2-	MOWING	AC	114.530
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	135,253.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	14,882.200
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	13,709.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	2,332.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45088315201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	4.275
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,259.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45088315201)	LS	1.000

Call Order: 002 Proposal: E1W98

ALT	Item	Description	Unit	Quantity
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,112.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,771.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	722.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.224
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	60.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,544.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.312
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,166.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	2.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	11.167
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.058
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.016
	0711- 16-171	THERMOPLASTIC, STANDARD OTHER SURFACES, WHITE, 6", 6-10 DOTTED MANAGED LANE MARKING	GM	0.219
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	11.185
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.052
Section 0003 Signalization				
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	23.000