

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01261105	Call Order: 002	Proposal: E1Y46	District:01
Counties:	OKEECHOBEE			
Road Name:	SR 710 FROM SR 70 TO N. OF INTERCEPTOR CREEK BRIDGE #910065			
Limits:	91060000			
Project(s):	45110615201(*)	Federal Aid No:	N/A	
Total Roadway Length:	1.057 Miles	Contract Days:	100	
Total Bridge Length:	0.044 Miles	Letting Date:	11/05/26	
Total Proposal Length:	1.101 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days(Acqui Time)	
Proposal Budget Estimate:	\$1,556,255.83			

Please read the full advertisement

Description:

The Improvements under this contract consist of milling and resurfacing, and pavement markings on SR 710 from SR 70 to North of Interceptor Creek Bridge in Okeechobee County.

Call Order: 002 Proposal: E1Y46

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45110615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45110615201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,600.000
	0102- 60-	WORK ZONE SIGN	ED	9,900.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	15,100.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	762.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	328.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	200.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	200.000
	0102-115-	TYPE III BARRICADE	ED	1,600.000
	0104- 10- 3	SEDIMENT BARRIER	LF	7,740.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	5.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	3.000
	0107- 1-	LITTER REMOVAL	AC	33.110
	0107- 2-	MOWING	AC	29.790
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	2.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	26,722.000
	0337- 7- 95	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, HIGH POLYMER	TN	2,939.400
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,896.000
	0570- 13- 1	SHOULDER DROP OFF SOIL	CY	500.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45110615201)	LS	1.000
Section 0002 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	762.000

Call Order: 002 Proposal: E1Y46

ALT	Item	Description	Unit	Quantity
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45110615201)	LS	1.000
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.086
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	146.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	415.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	145.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.026
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	26.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	15.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	1,151.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	102.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.334
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.066
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.852
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.087
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.104
Section 0003 Signalization				
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	2.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000