

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01261105	Call Order: 003	Proposal: E1Y47	District:01
Counties:	POLK			
Road Name:	SR 600 (US 92/US 17) FROM S OF SOUTH BLVD TO N OF NORTH BLVD			
Limits:	16050000			
Project(s):	45087615201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.964 Miles	Contract Days:	90	
Total Bridge Length:	0.000 Miles	Letting Date:	11/05/26	
Total Proposal Length:	0.964 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days(Acqui Time)	
Proposal Budget Estimate:	\$965,254.00			

Please read the full advertisement

Description:

The Improvements under this contract consist of milling and resurfacing, curb and gutter, sidewalk, and pavement markings on SR 600 (US 92/US 17) from South of South Boulevard to North of North Boulevard in Polk County.

Call Order: 003 Proposal: E1Y47

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45087615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45087615201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (45087615201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	180.000
	0102- 60-	WORK ZONE SIGN	ED	10,536.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	18,810.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	11,760.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	18.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	467.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	90.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	90.000
	0102-115-	TYPE III BARRICADE	ED	30.000
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	14.000
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	233.000
	0104- 10- 3	SEDIMENT BARRIER	LF	449.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	19.000
	0107- 1-	LITTER REMOVAL	AC	13.550
	0107- 2-	MOWING	AC	11.980
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	454.000
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	1,020.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	20,373.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	168.400

Call Order: 003 Proposal: E1Y47

ALT	Item	Description	Unit	Quantity
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	1,764.900
	0425- 5-	MANHOLE, ADJUST	EA	7.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	527.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	350.000
	0527- 2-	DETECTABLE WARNINGS	SF	362.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	412.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.136
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	950.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	47.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.272
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45087615201)	LS	1.000
Section 0002 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	414.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45087615201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	6.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	371.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.002
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	456.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	2,046.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	314.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.664
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.016
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.136
Section 0003 Signalization				
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	2.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000
	0671- 2- 40	TRAFFIC CONTROLLER, MODIFY	EA	1.000