

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01261015	Call Order: 001	Proposal: E1Y44	District:01
Counties:	POLK			
Road Name:	SR 35 (US 98) FROM N OF SR 546 TO S OF GRIFFIN RD			
Limits:	16210000			
Project(s):	45148015201(*)	Federal Aid No:	N/A	
Total Roadway Length:	1.723 Miles	Contract Days:	130	
Total Bridge Length:	0.000 Miles	Letting Date:	10/15/26	
Total Proposal Length:	1.723 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 days(Aqui Time)	
Proposal Budget Estimate:	\$3,675,833.91			

Please read the full advertisement

Description:

The Improvements under this contract consist of milling and resurfacing, curb ramps, and pavement markings on SR 35 (US 98) from North of SR 546 to South of Griffin Road in Polk County.

Call Order: 001 Proposal: E1Y44

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45148015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45148015201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	168.000
	0102- 60-	WORK ZONE SIGN	ED	10,140.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,920.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,780.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	132.000
	0102- 78- 2	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE B	EA	944.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	288.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	260.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	260.000
	0102-115-	TYPE III BARRICADE	ED	142.000
	0102-913- 23	REMOVABLE TAPE, WHITE, 24" STOP BAR	LF	16.000
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	43.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	83.000
	0107- 1-	LITTER REMOVAL	AC	58.530
	0107- 2-	MOWING	AC	30.980
	0110- 1- 1	CLEARING & GRUBBING (45148015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	100.000
	0327- 70- 3	MILLING EXISTING ASPHALT PAVEMENT, 4 1/2" AVG DEPTH	SY	13,368.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	14,767.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	11,280.000

Call Order: 001 Proposal: E1Y44

ALT	Item	Description	Unit	Quantity
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	28,992.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	7,410.500
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,643.600
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	121.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	79.000
	0527- 2-	DETECTABLE WARNINGS	SF	96.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	41.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.660
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.247
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	3,161.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	156.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,574.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.242
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.037
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	52.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	175.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.549
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	186.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.288
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45148015201)	LS	1.000
Section 0002 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	944.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45148015201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,161.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	156.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	599.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.037
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	123.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	186.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.288
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	975.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	52.000

Call Order: 001 Proposal: E1Y44

ALT	Item	Description	Unit	Quantity
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	52.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.660
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.247
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.242
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.549
	0714- 10-	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	3,172.000