

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	01260917	Call Order: 008	Proposal: E1Y81-R0	District:01
Counties:	DIST/ST-WIDE, MANATEE			
Road Name:	Miscellaneous Concrete			
Limits:	Midpoint			
Project(s):	43272827271(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	09/17/26	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:		

Proposal Budget Estimate: \$350,000.00

Please read the full advertisement

Description:

The work under this Contract consists of Miscellaneous Concrete

The award amount and contract bond shall be based on the Departments Budget Estimate amount of \$350,000.00 and not the contractors bid total

Prequalification is not required for this Contract.

Call Order: 008 Proposal: E1Y81-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	35.000
	0120- 1-	REGULAR EXCAVATION	CY	50.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	100.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	100.000
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	20.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	50.000
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	2.000
	0400- 2- 11	CONCRETE CLASS II, RETAINING WALLS	CY	2.000
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	5.000
	0415- 1- 6	REINFORCING STEEL- MISCELLANEOUS	LB	75.000
	0425- 5-	MANHOLE, ADJUST	EA	10.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	2.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	2.000
	0425- 14- 1	GRATE FOR EXISTING DRAINAGE STRUCTURE, FURNISH AND INSTALL	SF	2.000
	0425- 15- 41	INLET TOP, REPAIR, CURB INLET	EA	2.000
	0425- 15- 51	INLET TOP, REPLACE, CURB INLET	EA	2.000
	0425- 82-	REPLACE GRATE	EA	2.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	20.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	20.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	10.000
	0430-984-123	MITERED END SECTION, OPTIONAL ROUND, 15" SD	EA	5.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	5.000

Call Order: 008 Proposal: E1Y81-R0

ALT	Item	Description	Unit	Quantity
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	5.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	100.000
	0520- 1- 12	CONCRETE CURB & GUTTER, TYPE F WITH SPECIAL GUTTER PROFILE	LF	100.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	100.000
	0524- 1- 29	CONCRETE DITCH PAVEMENT, 4", REINFORCED	SY	50.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	50.000
	0524- 2- 29	CONCRETE SLOPE PAVEMENT, 4", REINFORCED	SY	50.000
	0524- 2- 49	CONCRETE SLOPE PAVEMENT, 6", REINFORCED	SY	10.000
	0527- 2-	DETECTABLE WARNINGS	SF	200.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	15.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	15.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	100.000
	E110- 70-	REMOVAL OF FLEXIBLE PAVEMENT	SY	20.000
	E425- 73- 3	FRAME AND GRATE (F&I)	EA	2.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	2.000
	E521- 1-	CONCRETE BARRIER WALL REPAIR	CY	5.000
	E522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS- REMOVE AND REPLACE, 4"	SY	250.000
	E522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS- REMOVE AND REPLACE, 6"	SY	555.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	100.000
	E575- 1-	SODDING	SY	275.000