

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02190417	Call Order: 003	Proposal: E2Y54	District:02
Counties:	LAFAYETTE, TAYLOR			
Road Name:	Desilting			
Limits:	Midpoint			
Project(s):	41021557222(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	04/17/19	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	00 Days (Acq. Time)	

Proposal Budget Estimate: \$250,000.00

Please read the full advertisement

Description:

Remove and dispose of silt, debris, vegetation, soil, rock, or any type of blockage inside a pipe, storm drain inlet or box culvert to provide maximum drainage capacity. To include furnishing all equipment, tools, labor, disposal of silt and debris, de-watering, erosion and pollution control, cleanup, Maintenance of Traffic (MOT), storm sewer inspection (video and mapping) to produce a video DVD and report, and all incidentals at various locations. BID EXPRESS MANDATORY.

Call Order: 003 Proposal: E2Y54

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	11,048.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	10,285.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	1,882.000
	0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	70.000
	0430- 94- 5	DESILTING PIPE, 61" OR GREATER	LF	588.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	23,873.000