

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 02190417 Call Order: 006 Proposal: E2Y99 District:02  
Counties: DUVAL  
Road Name: Storm Drain Pipe Replacement  
Limits: Midpoint  
Project(s): 41021677211(\*) Federal Aid No: N/A  
Total Roadway Length: 0.000 Miles Contract Days: 45  
Total Bridge Length: 0.000 Miles Letting Date: 04/17/19  
Total Proposal Length: 0.000 Miles Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 00 Days (Acq. Time)

Proposal Budget Estimate: \$250,000.00

Please read the full advertisement

Description:

Remove approximately 160 linear feet of the existing of 42-inch spirally reinforced aluminum steel pipe (SRASP), furnish and install new 42-inch reinforced concrete (RCP) class III pipe and connect it to the existing manhole Nos. S-320 and S-322. The pipe invert elevation is approximately 11.0 ft. below the existing finished grade. To facilitate the SRASP replacement, work will include the removal and replacement of the existing sidewalk, type "F" curb and gutter, and sodding of affected areas. Also included are flexible pavement and base reconstruction (bike path only), installation of thermoplastic pavement markings, coordination of all utility locates, manhole repair/adjustments and other restoration work within the project limits (see Appendix A). All works are located on Beach Boulevard eastbound east of Station Creek Road from sta. 502+00 to sta 503+60 in Duval County. The services under this Contract consists of furnishing all labor, materials, transportation, maintenance of traffic, excavation, backfill, dewatering, well pointing and equipment required to replace the 42-inch SRASP. LUMP SUM. BID EXPRESS MANDATORY.

**Call Order: 006 Proposal: E2Y99**

---

ALT	Item	Description	Unit	Quantity
	<b>Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF)</b>			
	E999- 10- 41	MAINTENANCE LUMP SUM CONTRACT	LS	1.000