Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02190417 Call Order: 007 Proposal: E2Z05 District:02

Counties: DUVAL

Road Name: Mathews Bridge Deck Repair

Limits: MIDPOINT

Project(s): 41022137211(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	04/17/19
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	00 Days (Acq. Time)

Proposal Budget Estimate: $650,000.00

Please read the full advertisement

Description:

Partial deck removal and replacement of the Mathews Bridge for the modification of existing stringers and diaphragms. Work includes using hydro-demolition for the removal of the deck at specified locations without damaging embedded reinforcement, installing shear studs on exposed stringers and diaphragms and recasting the deck. The Mathews is located on SR 10 A over the St. Johns River in Duval County. Experience in Bridge Repair (Form 850-070-04) must be completed and submitted with the bid. LUMP SUM. BID EXPRESS MANDATORY.
Special Bid Requirement: Samples of completed projects where hydro-demolition was employed successfully by the Contractor within the last 5 years;
A bid history of specific projects, quantities, dates of construction, bridge owner contact information, and personnel experience.
All welding & workmanship shall be in accordance with current version of Section 460, AASHTO/AWS D.15M/D1.5 Bridge Welding Code.

Call Order: 007 Proposal: E2Z05

ALT	Item	Description	Unit	Quantity
Section 0001 BRIDGE DECK MAINTENANCE AND REPAIR (SF)				
	E999- 10- 41	MAINTENANCE LUMP SUM CONTRACT	LS	1.000