

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02190220	Call Order: 007	Proposal: E2Z09	District:02
Counties:	DUVAL			
Road Name:	I-95 Slab Replacement			
Limits:	Midpoint			
Project(s):	41021687204(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	73	
Total Bridge Length:	0.000 Miles	Letting Date:	02/20/19	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	00 Days (Acq. Time)	
Proposal Budget Estimate:	\$1,050,000.00			

Please read the full advertisement

Description:

Subsurface polyurethane injection as described in the Developmental Specification and replacement of damaged concrete pavement slabs (approximately 28 slabs with average dimensions of 12 feet wide by 20 feet long each) on SR 9 I-95 southbound at the I-295 South Interchange as identified in Contract Plans Exhibit A. The contractor will be required to perform polyurethane injection prior to replacement of the damaged concrete pavement slabs (approximately 10 inches thick) as described in the Contract Plans and per FDOT Standard Plans for Road and Bridge Construction. Replace all pavement striping, retro-reflective pavement markers, and sod all disturbed areas within the project limits. Experience in Concrete Pavement Repair (Form 850-070 -02) must be completed and submitted with the bid. **BID EXPRESS MANDATORY.**

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 007 Proposal: E2Z09

ALT	Item	Description	Unit	Quantity
Section 0001 BASE REPAIR (TN)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	730.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,380.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	73.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	24.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	80.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	146.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	146.000
	0104- 10- 3	SEDIMENT BARRIER	LF	400.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	470.000
	0121- 70- 2	FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY	CY	314.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT:	LF	202.000
	0352- 70-	GRINDING CONCRETE PAVEMENT	SY	470.000
	0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	130.700
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.020
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	250.000
	0706- 3-	RETRO-REFLECTIVE/RAISED PAVEMENT MARKERS	EA	10.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.035
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.035
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.035
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.035
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.035
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.035
	9061-73 -19	TWO COMPONENT POLYURETHANE INJECTION, PROJECT 410216-8- 72-04	LB	25,000.000