

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	02190515	Call Order: 003	Proposal: E2Y27	District:02
Counties:	DUVAL			
Road Name:	SR 10 FM: TYLER ST. TO: EAVERSON ST			
Limits:	72010000			
Project(s):	44129815201(*)	Federal Aid No:	N/A	
Project(s):	44129815202	Federal Aid No:	N/A	
Project(s):	44129815601	Federal Aid No:	N/A	
Total Roadway Length:	1.404 Miles	Contract Days:	360	
Total Bridge Length:	0.000 Miles	Letting Date:	05/15/19	
Total Proposal Length:	1.404 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days (Acq. Time)	

Proposal Budget Estimate: \$2,126,030.00

Please read the full advertisement

**Description:**

(SR 10 (Beaver Street) from East of Tyler Street to East of Eaverson Street) Milling and Resurfacing, Base Work, Drainage Improvements, Curb and Gutter, Traffic Signals, Highway Signing, Sidewalk Improvements, JEA Utility Work and other incidental construction on SR 10 /US 90 (Beaver Street) in Duval County from East of Tyler Street to East of Eaverson Street. JEA Table - A must be completed and submitted with the bid. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

**Call Order: 003 Proposal: E2Y27**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44129815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44129815201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,050.000
	0102- 60-	WORK ZONE SIGN	ED	24,615.000
	0102- 61-	BUSINESS SIGN	EA	11.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	1,056.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	804.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	18,885.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	4,290.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	355.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	255.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	59.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,280.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	720.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	720.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	18.000
	0107- 1-	LITTER REMOVAL	AC	14.170
	0107- 2-	MOWING	AC	3.400
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44129815201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44129815201)	LS	1.000

**Call Order: 003 Proposal: E2Y27**

ALT	Item	Description	Unit	Quantity
	0110- 1- 1	CLEARING & GRUBBING (44129815202)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,427.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	36.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44129815201)	LS	1.000
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44129815202)	LS	1.000
	0121- 70- 5	FLOWABLE FILL, PAVEMENT REPAIRS, PROJECT 441298-1-52-02	CY	99.000
	0285-714-	OPTIONAL BASE, BASE GROUP 14	SY	119.000
	0327- 70- 5	MILLING EXIST ASPH PAVT, 2" AVG DEPTH	SY	8,734.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	1,567.000
	0327- 70- 7	MILLING EXIST ASPH PAVT, 4" AVG DEPTH	SY	2,213.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	774.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,044.500
	0425- 1-205	INLETS, CURB, TYPE 9, PARTIAL	EA	2.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	4.000
	0425- 1-355	INLETS, CURB, TYPE P-5, PARTIAL	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	5.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0425- 4-	INLETS, ADJUST	EA	7.000
	0425- 5-	MANHOLE, ADJUST	EA	10.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	13.000
	0425- 6-	VALVE BOXES, ADJUST	EA	16.000
	0425- 82-	REPLACE GRATE	EA	4.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	600.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	600.000
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	71.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	19.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	731.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	25.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	7.000
	0431- 1-213	PIPE LINING- CIPP- INVERSION RESIN IMPREGNATED FELT, 18" PROJECT 441298-1-52-02	LF	492.000
	0431- 1-214	PIPE LINING- CIPP- INVERSION RESIN IMPREGNATED FELT, 30" PROJECT 441298-1-52-02	LF	17.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	2,036.000
	0520- 3-	VALLEY GUTTER- CONCRETE	LF	102.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,037.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	661.000
	0522- 4-	BUS SHELTER PAD- CONCRETE	SY	159.000
	0527- 2-	DETECTABLE WARNINGS	SF	351.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	487.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.932
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	212.000

**Call Order: 003 Proposal: E2Y27**

ALT	Item	Description	Unit	Quantity
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.517
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	6.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	6.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.046
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44129815201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44129815201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,089.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	290.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.051
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	6.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.026
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	631.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.965
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.709
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.306
<b>Section 0003 Signalization</b>				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	374.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	1,735.000
	0632- 7- 7	SIGNAL CABLE, REMOVE- OUTSIDE OF INTERSECTION	LF	340.000
	0633- 1-420	FIBER OPTIC CABLE, RELOCATE, UNDERGROUND	LF	200.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0639- 1-420	ELECTRICAL POWER SERVICE, RELOCATE, UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	185.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	180.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	5.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	3.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	3.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	5.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	15.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	16.000

Call Order: 003 Proposal: E2Y27

ALT	Item	Description	Unit	Quantity
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	14.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	12.000
<b>Section 0004 Utilities</b>				
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44129815601)	LS	1.000
	1000- 6-	UTILITY WORK- JPA/UTILITY AGREEMENT, WATER (44129815601)	LS	1.000