

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 02181114 Call Order: 002 Proposal: E2X68 District:02
Counties: COLUMBIA
Road Name: I-10 (SR8) @ US 441 INTERCHANGE
Limits: 29170000
Project(s): 43500015201(*) Federal Aid No: N/A
Total Roadway Length: 0.644 Miles Contract Days: 125
Total Bridge Length: 0.000 Miles Letting Date: 11/14/18
Total Proposal Length: 0.644 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 120 Days (Acq. Time)
Proposal Budget Estimate: \$957,501.55

Please read the full advertisement

Description:

(I-10 (SR 8) @ US 441 Interchange) Lighting and other incidental construction on SR 8 (I-10) @ US 441 interchange.
PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 002 Proposal: E2X68

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43500015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43500015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	14,250.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	125.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	500.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,382.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,540.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43500015201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	4,924.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	919.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	382.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	36.000
	0635- 3- 11	JUNCTION BOX, FURNISH & INSTALL, AERIAL	EA	10.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	874.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	19,758.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	1,427.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	4.000
	0715- 19- 13	HIGH MAST LIGHT POLE, FURNISH AND INSTALL, 120'	EA	11.000
	0715-500- 2	POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST	EA	11.000