

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 02181114      Call Order: 004      Proposal: E2Y01      District:02

Counties: GILCHRIST

Road Name: lump sum contract to mill and place compacted asphalt,

Limits:

Project(s): 41021827210

Federal Aid No: N/A

Total Roadway Length:

0.000 Miles

Contract Days:

45

Total Bridge Length:

0.000 Miles

Letting Date:

11/14/18

Total Proposal Length:

0.000 Miles

Contract Execution Days:

10

Special Start Date:

N/A

Aquis/Flexible Start Time:

00 Days (Acq. Time)

Proposal Budget Estimate:

\$325,000.00

Please read the full advertisement

Description:

Supply materials, equipment, labor and incidentals to mill, place and compact asphalt concrete and install thermoplastic striping and symbols, and RPM's on North and South bound lanes and shoulders of State Road 47 starting at Mile Post 2.06 to Mile Post 3.86. Road has 12' lane widths and 5' paved shoulders. Mill to a depth of 1.5 inches (match existing cross slope) and replace with 1.5 inches of FC-12.5 (Traffic Level C) with PG76-22 Binder. LUMP SUM. BID EXPRESS MANDATORY.

**Call Order: 004 Proposal: E2Y01**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)</b>				
	E999- 10- 41	MAINTENANCE LUMP SUM CONTRACT	LS	1.000