

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02181017	Call Order: 001	Proposal: E2X67	District:02
Counties:	CLAY			
Road Name:	SR21(BLANDING BLVD)			
Limits:	71070000			
Project(s):	20821185201(*)	Federal Aid No:	N/A	
Total Roadway Length:	1.779 Miles	Contract Days:	800	
Total Bridge Length:	0.004 Miles	Letting Date:	10/17/18	
Total Proposal Length:	1.783 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days (Acq. time)	
Proposal Budget Estimate:	\$19,755,438.02			

Please read the full advertisement

Description:

(SR 21 (Blanding Blvd) from CR 220 (Long Bay Rd) to Allie Murray Road) Roadway Milling & Resurfacing, Base Work, Shoulder Treatment, Drainage Improvements, Curb & Gutters, Traffic Signals, Lighting, Highway Signing, Box Culverts, Sidewalks/Bicycle Path, and other incidental construction on SR 21 (Blanding Blvd.) in Clay County from CR 220 (Long Bay Rd.) to Allie Murray Road. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

Call Order: 001 Proposal: E2X67

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 2- 1	CONCRETE CLASS II, CULVERTS	CY	98.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	17,635.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (20821185201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (20821185201)	LS	1.000
	0102- 2- 1	SPECIAL DETOUR 1 (20821185201)	LS	1.000
	0102- 2- 2	SPECIAL DETOUR 2 (20821185201)	LS	1.000
	0102- 2- 3	SPECIAL DETOUR 3 (20821185201)	LS	1.000
	0102- 2- 4	SPECIAL DETOUR 4 (20821185201)	LS	1.000
	0102- 2- 5	SPECIAL DETOUR 5 (20821185201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	128.000
	0102- 60-	WORK ZONE SIGN	ED	46,558.000
	0102- 61-	BUSINESS SIGN	EA	11.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	17,232.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	24,876.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	76,010.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	24,968.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	16,542.000
	0102- 75- 1	TEMPORARY SEPARATOR, F&I REMOVE	LF	11,402.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	410.000
	0102- 78-	TEMPORARY RETROREFLECTIVE PAVEMENT MARKER	EA	2,613.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	1,748.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	1,850.000

Call Order: 001 Proposal: E2X67

ALT	Item	Description	Unit	Quantity
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	1,850.000
	0102-911- 2	PAVEMENT MARKING REMOVABLE TAPE, WHITE OR BLACK,SOLID	LF	509.000
	0102-912- 2	PAVEMENT MARKING REMOVABLE TAPE, YELLOW, SOLID	LF	259.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	970.000
	0104- 9-	SEDIMENT BASIN / CONTAINMENT SYSTEM- CLEANOUT	EA	5.000
	0104- 10- 3	SEDIMENT BARRIER	LF	13,279.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	165.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	870.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	7.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	99.000
	0107- 1-	LITTER REMOVAL	AC	1,137.540
	0107- 2-	MOWING	AC	711.350
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (20821185201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (20821185201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	11,362.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	14.000
	0120- 1-	REGULAR EXCAVATION	CY	161,533.000
	0120- 4-	SUBSOIL EXCAVATION	CY	14,638.000
	0120- 6-	EMBANKMENT	CY	51,556.000
	0160- 4-	TYPE B STABILIZATION	SY	119,494.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,072.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	1,634.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	101,999.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	5,740.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	5,216.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	20,879.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	9,530.500
	0400- 2- 2	CONCRETE CLASS II, ENDWALLS	CY	13.200
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	1,170.000
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	50.000
	0425- 1-352	INLETS, CURB, TYPE P-5, >10'	EA	1.000
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	15.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	4.000
	0425- 1-452	INLETS, CURB, TYPE J-5, >10'	EA	1.000
	0425- 1-461	INLETS, CURB, TYPE J-6, <10'	EA	4.000
	0425- 1-471	INLETS, CURB, TYPE 7, <10'	EA	7.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	4.000
	0425- 1-529	INLETS, DT BOT, TYPE C, MODIFY	EA	2.000
	0425- 1-541	INLETS, DT BOT, TYPE D, <10'	EA	7.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 1-559	INLETS, DT BOT, TYPE E, MODIFY	EA	1.000
	0425- 1-589	INLETS, DT BOT, TYPE H, MODIFY	EA	1.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	4.000

Call Order: 001 Proposal: E2X67

ALT	Item	Description	Unit	Quantity
	0425- 2- 62	MANHOLES, P-8, >10'	EA	2.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	6.000
	0425- 2- 92	MANHOLES, J-8, >10'	EA	4.000
	0425- 5-	MANHOLE, ADJUST	EA	3.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0430-174-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD	LF	130.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	61.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	208.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	23.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	6,007.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	4,846.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	2,625.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	1,964.000
	0430-175-142	PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD	LF	117.000
	0430-175-166	PIPE CULVERT, OPT MATERIAL, ROUND, 66"S/CD	LF	18.000
	0430-175-230	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 30"S/CD	LF	23.000
	0430-612-133	U-ENDWALL, GRATE, STD 261, 1:4 SLOPE, 30" PIPE	EA	1.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	3.900
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	4.000
	0430-982-129	MITERED END SECTION, OPTIONAL ROUND, 24" CD	EA	1.000
	0430-982-133	MITERED END SECTION, OPTIONAL ROUND, 30" CD	EA	2.000
	0430-982-138	MITERED END SECTION, OPTIONAL ROUND, 36" CD	EA	2.000
	0430-982-140	MITERED END SECTION, OPTIONAL ROUND, 42" CD	EA	1.000
	0430-982-633	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 30" CD	EA	2.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	6.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	10,023.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	18,399.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	67.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	115.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	3,473.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	360.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	11,622.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,408.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	28.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	247.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	11.000
	0527- 2-	DETECTABLE WARNINGS	SF	553.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	342.100
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	103.300
	0530- 74-	BEDDING STONE	TN	176.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	27.000
	0550- 60-233	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 12.1-18' OPENING	EA	1.000

Call Order: 001 Proposal: E2X67

ALT	Item	Description	Unit	Quantity
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	97,045.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	9.883
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	506.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	811.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	6.322
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	65.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	7.996
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	49.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.054
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (20821185201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	72.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	30.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	60.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	3.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	1.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	15.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	14.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	6.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	94.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (20821185201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.836
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,500.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,413.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	934.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.474
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	20.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	123.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.195
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,464.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.029
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	54.000

Call Order: 001 Proposal: E2X67

ALT	Item	Description	Unit	Quantity
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	122.000
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.018
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	2.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	5.822
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	6.551
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	4.321
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.031
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.132
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.294
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.135
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.294
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	11,788.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	2,659.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	92.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	164.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	3.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	50,184.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	1,047.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	13.000
	0715- 4- 15	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT	EA	71.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	4.000
	0715- 5- 31	LUMINAIRE & BRACKET ARM- ALUMINUM, FURNISH & INSTALL NEW LUMINAIRE AND ARM ON NEW/EXISTING POLE	EA	4.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	88.000
Section 0005 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	9,717.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	5,416.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	930.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	3.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	2.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	400.000

Call Order: 001 Proposal: E2X67

ALT	Item	Description	Unit	Quantity
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	13,295.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	192.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	96.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	4.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	14.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	8.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	4.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	50.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	22.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	4.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 1-610	ELECTRICAL POWER SERVICE, REMOVE OVERHEAD	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	150.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	6.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	11.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	3.000
	0649- 21- 3	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 40'	EA	1.000
	0649- 21- 9	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 50'-50'	EA	1.000
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 21- 14	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 60'-60'	EA	1.000
	0649- 21- 15	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 70'	EA	2.000
	0649- 21- 18	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, DOUBLE ARM 70'-50'	EA	1.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	31.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	2.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	16.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	16.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	38.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	12.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	16.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	3.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	2.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	3.000

Call Order: 001 Proposal: E2X67

ALT	Item	Description	Unit	Quantity
	0685- 1- 12	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION	EA	3.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	5.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	10.000