

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 02191113 Call Order: 002 Proposal: E2Y59 District:02

Counties: LEVY

Road Name: Mill and repave asphalt at otter creek on us 19

Limits:

Project(s): 41021827214

Federal Aid No: N/A

Total Roadway Length:

0.000 Miles

Contract Days:

45

Total Bridge Length:

0.000 Miles

Letting Date:

11/13/19

Total Proposal Length:

0.000 Miles

Contract Execution Days:

10

Special Start Date:

N/A

Aquis/Flexible Start Time:

00 Days (Acq. Time)

Proposal Budget Estimate:

\$250,000.00

Please read the full advertisement

Description:

Supply materials, equipment, labor and incidents to mill, place and compact asphalt concrete and install thermoplastic striping and symbols, and RPM's on North and South bound lanes and shoulders of US 19 at M.P. 24.09 (Otter Creek) and M.P. 23.0. Mill to a depth of ¾ inches (match existing cross slope) and replace with ¾ inches of FC-5 (Traffic Level C) with PG76-22 Binder as specified in the plans. LUMP SUM. BID EXPRESS MANDATORY.

Call Order: 002 Proposal: E2Y59

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	E999- 10- 41	MAINTENANCE LUMP SUM CONTRACT (Lump sum contract to mill and repave loactions on us 19)	LS	1.000