

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02191113	Call Order: 005	Proposal: E2Y85	District:02
Counties:	DISTRICT-WIDE			
Road Name:	I-10 FORCEMAIN & EB BAKER CO REST AREA IMPROVEMENTS			
Limits:	27090121			
Project(s):	43865025201(*)	Federal Aid No:	N/A	
Project(s):	43865025202	Federal Aid No:	N/A	
Total Roadway Length:	29.794 Miles	Contract Days:	300	
Total Bridge Length:	0.000 Miles	Letting Date:	11/13/19	
Total Proposal Length:	29.794 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	45 Days (Acq. time)	
Proposal Budget Estimate:	\$4,430,189.00			

Please read the full advertisement

Description:

(I-10 Baker County forcemain Eastbound Rest Area Improvements) Install approximately 75,000 linear feet of new wastewater forcemain and other incidental construction from the I-10 (SR 8) Baker County Eastbound Rest Area to the City of Lake City wastewater collection system located approximately 200 feet south of the interchange of I-10 (SR 8) with SR 47 (US 441).
PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 005 Proposal: E2Y85

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43865015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43865015201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43865025201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,000.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	48,000.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	1,600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	300.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	600.000
	0104- 10- 3	SEDIMENT BARRIER	LF	63,955.000
	0110- 1- 1	CLEARING & GRUBBING (43865025201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	39.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	900.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	39.000
	0570- 1- 1	PERFORMANCE TURF	SY	70,871.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,459.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43865025201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43865025202)	LS	1.000
Section 0002 Utilities				
	1050- 31-204	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 4"	LF	63,827.000
	1050- 31-206	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 6"	LF	11,767.000
	1050- 31-210	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 10"	LF	1,450.000
	1050- 31-212	UTILITY PIPE- POLY VINYL CHLORIDE, FURNISH & INSTALL, WATER/SEWER, 12"	LF	1,450.000
	1050- 43-306	UTILITY PIPE- MEDIUM DENSITY POLYETHYLENE, FURNISH & INSTALL, GAS, 6"	LF	1,450.000
	1055- 11-454	UTILITY FITTINGS, F&I, DI/CI, CAP/PLUG, 8 - 19.9"	EA	4.000
	1060- 11-221	UTILITY STRUCTURE, BELOW GROUND, F&I, WATER / SEWER > 80 FT3, 0 - 6'	EA	1.000
	1060- 11-222	UTILITY STRUCTURE, BELOW GROUND, F&I, WATER / SEWER > 80 FT3, 6.1 - 12'	EA	1.000
	1080- 21-104	UTILITY FIXTURE, VALVE/METER BOX, FURNISH & INSTALL, 4"	EA	1.000
	1080- 24-104	UTILITY FIXTURE, VALVE ASSEMBLY, FURNISH AND INSTALL, 4"	EA	1.000
	1080- 26-102	UTILITY FIXTURE, VAC/AIR ASSEMBLY, FURNISH & INSTALL 2"	EA	41.000
	1080- 33-104	UTILITY FIXTURE, PLUG VALVE, FURNISH AND INSTALL 4"	EA	1.000
	1501- 1-	LIFT STATION, SANITARY SEWER	EA	1.000