

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 02191016 Call Order: 004 Proposal: E2Z22 District:02  
 Counties: HAMILTON  
 Road Name: WHITE SPRINGS WEIGH STATIONS - SIGNING AND PAVEMENT MARKINGS  
 Limits: 32100000  
 Project(s): 44199725215(\*) Federal Aid No: N/A  
 Total Roadway Length: 3.452 Miles Contract Days: 50  
 Total Bridge Length: 0.000 Miles Letting Date: 10/16/19  
 Total Proposal Length: 3.452 Miles Contract Execution Days: 10  
 Special Start Date: N/A  
 Aquis/Flexible Start Time: 15 Days (Acq. Time)  
 Proposal Budget Estimate: \$450,281.79

Please read the full advertisement

**Description:**

(White Springs Weigh Stations) Highway Signing, Pavement Marking and other incidental construction at the Weigh Station on SR 93/ I-75. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

**Call Order: 004 Proposal: E2Z22**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44199725215)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44199725215)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	500.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	100.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	50.000
	0107- 1-	LITTER REMOVAL	AC	34.790
	0107- 2-	MOWING	AC	25.610
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44199725215)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	96.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	38.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	114.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	4.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	4.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	22.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0700- 11-162	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- AC POWERED, SPEED FEEDBACK W/FLASHING BEACON, 12-20 SF	AS	2.000
	0700- 12- 11	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, ONE BEACON	AS	2.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	1,298.000
	0709- 12-110	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 6", PROJECT 441997-2-52-15	GM	5.657

**Call Order: 004 Proposal: E2Z22**

ALT	Item	Description	Unit	Quantity
	0709- 12-111	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 8", PROJECT 441997-2-52-15	GM	1.050
	0709- 12-112	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK, PROJECT 441997-2-52-15	LF	368.000
	0709- 12-113	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON, PROJECT 441997-2-52-15	LF	1,823.000
	0709- 12-114	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 24" FOR CROSSWALK, PROJECT 441997-2-52-15	LF	455.000
	0709- 12-115	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SKIP, 6", PROJECT 441997-2-52-15	GM	0.182
	0709- 12-116	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, YELLOW, SOLID, 6", PROJECT 441997-2-52-15	GM	3.481
	0709- 12-117	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, YELLOW, SOLID 8" FOR INTERCH & URBAN ISLAND, PROJECT 441997-2-52-15	GM	0.261
	0709- 12-118	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON, PROJECT 441997-2-52-15	LF	650.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	185.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	81.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	611.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	6.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	12.000
	0711- 17-	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS: NON-CONFLICTING ONLY	SF	34,344.000