

## Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

---

Letting: 02201216	Call Order: 003	Proposal: E20B6	District:02
Counties: NASSAU			
Road Name: YULEE WEIGH STATION - MCCO WEIGH STATION STATIC/WIM			
Limits: 74160000			
Project(s): 44199825215(*)	Federal Aid No: N/A		
Project(s): 44199835216	Federal Aid No: N/A		
Total Roadway Length:	5.630 Miles	Contract Days:	180
Total Bridge Length:	0.000 Miles	Letting Date:	12/16/20
Total Proposal Length:	5.630 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	120 Days (acq. time)
Proposal Budget Estimate:	\$2,125,458.00		

Please read the full advertisement

Description:

(Yulee Weigh Station; Lighting and Electrical) Highway Signing, Pavement Marking, Roadway Lighting and other incidental construction at the NB & SB Weigh Station on SR 9 (I-95). PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

### Call Order: 003 Proposal: E20B6

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44199825215)	LS	1.000
	0101- 1-	MOBILIZATION (44199835216)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44199825215)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,800.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,000.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	180.000
	0102-115-	TYPE III BARRICADE	ED	360.000
	0104- 10- 3	SEDIMENT BARRIER	LF	7,338.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	11.000
	0107- 1-	LITTER REMOVAL	AC	323.350
	0107- 2-	MOWING	AC	222.570
	0110- 1- 1	CLEARING & GRUBBING (44199835216)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	35.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	32.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44199825215)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44199835216)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	96.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	36.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	106.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	4.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	4.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	24.000

**Call Order: 003 Proposal: E20B6**

ALT	Item	Description	Unit	Quantity
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0700- 11-262	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- SOLAR POWERED, SPEED FEEDBACK W/FLASHING BEACON, 12-20 SF	EA	2.000
	0700- 11-600	ELECTRONIC DISPLAY SIGN, REMOVE- GROUND MOUNT	AS	1.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	2.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	1,110.000
	0709- 12-101	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 6", PROJECT 441998-2-52-15	GM	5.478
	0709- 12-102	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 8", PROJECT 441998-2-52-15	GM	1.022
	0709- 12-103	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK, PROJECT 441998-2-52-15	LF	144.000
	0709- 12-104	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON, PROJECT 441998-2-52-15	LF	1,736.000
	0709- 12-105	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 24" FOR CROSSWALK, PROJECT 441998-2-52-15	LF	319.000
	0709- 12-106	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SKIP, 6", PROJECT 441998-2-52-15	GM	0.276
	0709- 12-107	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, YELLOW, SOLID, 6", PROJECT 441998-2-52-15	GM	3.382
	0709- 12-108	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, YELLOW, SOLID 8" FOR INTERCH & URBAN ISLAND, PROJECT 441998-2-52-15	GM	0.280
	0709- 12-109	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON, PROJECT 441998-2-52-15	LF	852.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	156.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	84.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	561.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	6.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	12.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	34,744.000
<b>Section 0003 Lighting</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	24,878.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,147.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	164.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	2.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	35,493.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	65,694.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	26,705.000

**Call Order: 003 Proposal: E20B6**

ALT	Item	Description	Unit	Quantity
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	144.000
	0715- 4- 70	LIGHT POLE COMPLETE, REMOVE POLE AND FOUNDATION	EA	136.000
	0715- 5- 51	LUMINAIRE & BRACKET ARM, REMOVE LUMINAIRE AND ARM; POLE REMAINS	EA	4.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	2.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	2.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	144.000