

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02200318	Call Order: 011	Proposal: E2Z37	District:02
Counties:	TAYLOR			
Road Name:	SR 55 (US 19) - DRAINAGE IMPROVEMENTS			
Limits:	38010000			
Project(s):	43616525201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.250 Miles	Contract Days:	90	
Total Bridge Length:	0.000 Miles	Letting Date:	03/18/20	
Total Proposal Length:	0.250 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60 Days (Acq. Time)	

Proposal Budget Estimate: \$319,578.00

Please read the full advertisement

Description:

(SR 55 (US 19) from BMP 26.500 to EMP 26.750) Drainage improvements, curb & gutter, guardrail, and other incidental construction on SR 55 (US 19). PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

Call Order: 011 Proposal: E2Z37

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43616525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43616525201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,080.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,400.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	90.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	180.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	27.000
	0104- 10- 3	SEDIMENT BARRIER	LF	570.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	30.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	1.650
	0107- 2-	MOWING	AC	1.650
	0110- 1- 1	CLEARING & GRUBBING (43616525201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	48.000
	0400- 1- 2	CONCRETE CLASS I, ENDWALLS	CY	5.300
	0425- 1-523	INLETS, DT BOT, TYPE C,JBOT, <10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	2.000
	0430-175-248	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 48"S/C	LF	570.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	80.600
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	50.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	39.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	25.000
	0536- 73-	GUARDRAIL REMOVAL	LF	29.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	2,642.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43616525201)	LS	1.000