

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 012 Proposal: E2Z50

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	50.000
	0413-151-	METHACRYLATE MONOMER	GA	512.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	51,178.000
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	250.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	120.000
	0506- 2-	BRIDGE DRAINAGE PIPE	LF	1,726.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (42848915201 720087)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (42848915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42848915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	560.000
	0102- 60-	WORK ZONE SIGN	ED	12,280.000
	0102- 62-	BARRIER MOUNTED WORK ZONE SIGN- INDEX 11871/700-013	ED	3,840.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,300.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	1,020.000
	0102- 74- 7	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	LF	480.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	170.000
	0350- 5-	CLEANING & SEALING JOINTS- CONCRETE PAVEMENT	LF	2,700.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42848915201)	LS	1.000
Section 0003 Lighting				
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	9,600.000
	0630- 2- 65	CONDUIT, REMOVE, BRIDGE MOUNT	LF	9,600.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	58.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	58.000