Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02210421 Call Order: 001 Proposal: E20A2-R0 District:02

Counties: DISTRICT-WIDE

Road Name: De-silting box culverts with repairs

Limits: Midpoint

Project(s): 41022137214(*) Federal Aid No: N/A

Project(s): 41022147212 Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	04/21/21
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	00 Days (acq. time)

Proposal Budget Estimate: $750,000.00

Please read the full advertisement

Description:

Remove and dispose of silt, debris, vegetation, soil, rock, or any type of blockage inside a pipe or box culvert to restore maximum drainage capacity. As directed by the Engineer, furnish, and install weep hole filters, repair cracks, and repair other deficiencies as directed in the Work Documents. EXPERIENCE IN BRIDGE REPAIR (Form 850-070-04) must be completed and submitted with the bid. RENEWAL OPTION. BID EXPRESS MANDATORY.

Call Order: 001 Proposal: E20A2-R0

ALT	Item	Description	Unit	Quantity
Section 0001 SUBSTRUCTURE MAINTENANCE/REPAIR (MH)				
	0400-150-	CLEANING AND SEALING EXISTING CONCRETE SURFACE	SF	93.000
	0400-153-	NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB	CF	52.000
	0401- 71- 11	RESTORE SPALLED AREAS- MAINTENANCE CONTRACTS ONLY, GUNITE, OVER LAND AND <= 20' BRIDGE HEIGHT	CF	8.750
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	39.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	28.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	6,464.620
	0530- 1-	RIPRAP, SAND-CEMENT	CY	9.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	14.000
	E430- 50- 2	WEEP HOLE FILTER , CONTRACT E20A2	LS	1.000