

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	02210120	Call Order: 002	Proposal: E20C7	District:02
Counties:	DUVAL			
Road Name:	- BRIDGE-REPAIR/REHABILITATION			
Limits:	72001000			
Project(s):	42442115201(*)	Federal Aid No:	N/A	
Total Roadway Length:	3.409 Miles	Contract Days:	350	
Total Bridge Length:	1.989 Miles	Letting Date:	01/20/21	
Total Proposal Length:	5.398 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days (Acq. time)	
Proposal Budget Estimate:	\$3,021,512.00			

Please read the full advertisement

Description:

(Duval Bridges Repair Fender & Nav Light Systems #0022, 0249, 0343) Fender system and navigational lighting and other incidental construction repairs on the SR 5/Main St. over St Johns River Bridge (Br No. 720022) and I- 295/ Buckman Bridge over St Johns River (SB Br No. 720249, NB Br No. 720343). PRE-QUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 002 Proposal: E20C7**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 71- 1	BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL	LF	844.000
	0401- 70- 2	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- STYRENE BUTADIENE	CF	13.000
	0455- 34- 2	PRESTRESSED CONCRETE PILING, 14" SQ.	LF	630.000
	0455- 76-	WRAP PILE CLUSTERS	EA	256.000
	0460- 1- 2	STRUCT STEEL, REHAB, LOW ALLOY	LB	3,046.000
	0460- 1- 13	STRUCTURAL STEEL REHAB- BOLTS, NUTS, WASHERS & PLATES	LB	12,648.000
	0460-112-	ANCHOR BOLT REPLACEMENT	EA	17.000
	0460-112-100	ANCHOR BOLT REPLACEMENT, UNDERWATER PROJECT 424421-1-1-52-01	EA	40.000
	0470- 1-	TREATED TIMBER, STRUCTURAL	MB	21.200
	0471- 1- 1	FENDER SYSTEM,PLASTIC MARINE LUMBER,REINFORCED	MB	20.000
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (42442115201 720022)	LS	1.000
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (42442115201 720249)	LS	1.000
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (42442115201 720343)	LS	1.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (42442115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42442115201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,782.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	16,464.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,088.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	526.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	582.000
	0104- 11-	FLOATING TURBIDITY BARRIER (Bridges 720022, 720249 & 720343)	LF	1,810.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (Bridges 720249 & 720343)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (42442115201)	LS	1.000