

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02210721 Call Order: 002 Proposal: E20F7 District:02
 Counties: DUVAL
 Road Name: I-95(SR9) OVER NASSAU RIVER BRIDGES
 Limits: 72290000
 Project(s): 43920115201(*) Federal Aid No: N/A
 Total Roadway Length: 0.236 Miles Contract Days: 450
 Total Bridge Length: 0.236 Miles Letting Date: 07/21/21
 Total Proposal Length: 0.472 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Days (acq. time)

Proposal Budget Estimate: \$7,888,681.00

Please read the full advertisement

Description:

(I-95 (SR 9) over Nassau River Bridges No. 720218 & No. 720336) Bridge structural rehabilitation and other incidental construction on SR 9 over Nassau River. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

Call Order: 002 Proposal: E20F7

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 3- 20	CONC CLASS III, SEAL	CY	174.000
	0400- 8-107	CONC CLASS V, MICROSILICA SUBSTRUCTURE MASS	CY	1,618.000
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	20.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	189,154.000
	0455- 88- 5	DRILLED SHAFT, 48" DIA	LF	2,180.000
	0455-107- 5	DRILLED SHAFT CASING, 48" DIAMETER	LF	1,377.000
	0455-122- 5	EXCAVATION UNCLASSIFIED SHAFT, 48" DIA	LF	2,015.000
	0455-147- 1	THERMAL INTEGRITY TESTING, UP TO 4' SHAFT DIAMETER	EA	28.000
	0462- 2- 23	POST TENSIONING TENDONS, SUBSTRUCTURE STRAND FLEXIBLE FILLER	LB	106,260.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43920115201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43920115201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (43920115201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (43920115201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	4,360.000
	0102- 60-	WORK ZONE SIGN	ED	7,888.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	1,958.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	1,958.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	54,988.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	436.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	4.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	900.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	872.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	872.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	1.510

Call Order: 002 Proposal: E20F7

ALT	Item	Description	Unit	Quantity
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.504
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.882
	0104- 10- 3	SEDIMENT BARRIER	LF	5,870.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	4,130.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (43920115201)	LS	1.000
	0108- 2-	MONITOR EXISTING STRUCTURES- VIBRATION MONITORING (43920115201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (43920115201)	LS	1.000
	0125- 1-	EXCAVATION FOR STRUCTURES	CY	433.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	4,333.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	24,373.000
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	357.500
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	1,468.900
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.719
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,736.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	6,412.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.797
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.966
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	3.673
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43920115201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	524.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43920115201)	LS	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	1.732
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.462
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.732
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.252
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.504
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.252
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.252