

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

| | | | | |
|---------------------------|-------------------|----------------------------|---------------------|-------------|
| Letting: | 02210609 | Call Order: 001 | Proposal: E20C5 | District:02 |
| Counties: | BRADFORD | | | |
| Road Name: | - BIKE PATH/TRAIL | | | |
| Limits: | Midpoint | | | |
| Project(s): | 43317145201(*) | Federal Aid No: N/A | | |
| Total Roadway Length: | 0.000 Miles | Contract Days: | 180 | |
| Total Bridge Length: | 0.006 Miles | Letting Date: | 06/09/21 | |
| Total Proposal Length: | 0.006 Miles | Contract Execution Days: | 10 | |
| | | Special Start Date: | N/A | |
| | | Aquis/Flexible Start Time: | 15 Days (acq. time) | |
| Proposal Budget Estimate: | \$1,703,258.00 | | | |

Please read the full advertisement

Description:

(CR 18 from SE 36th Avenue to CR 325) Base Work, Shoulder Treatment, Drainage Improvements, Highway Signing, Box Culvert, Bicycle Paths, and other incidental construction on CR 18 Rail to Trail in Bradford County from CR 325 to SE 36th Ave. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

Call Order: 001 Proposal: E20C5

| ALT | Item | Description | Unit | Quantity |
|--------------------------------|--------------|---|------|------------|
| Section 0001 Structures | | | | |
| | 0110- 3- | REMOVAL OF EXISTING STRUCTURES/BRIDGES (43317145201) | LS | 1.000 |
| | 0400- 4- 1 | CONCRETE CLASS IV, CULVERTS | CY | 206.700 |
| | 0415- 1- 1 | REINFORCING STEEL- ROADWAY | LB | 45,286.000 |
| | 0530- 3- 3 | RIPRAP- RUBBLE, BANK AND SHORE | TN | 180.800 |
| | 0530- 74- | BEDDING STONE | TN | 64.400 |
| Section 0002 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (43317145201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (43317145201) | LS | 1.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 6,300.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 1,920.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 720.000 |
| | 0102-115- | TYPE III BARRICADE | ED | 3,600.000 |
| | 0104- 10- 3 | SEDIMENT BARRIER | LF | 17,498.000 |
| | 0104- 11- | FLOATING TURBIDITY BARRIER | LF | 72.000 |
| | 0104- 15- | SOIL TRACKING PREVENTION DEVICE | EA | 10.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 14.060 |
| | 0107- 2- | MOWING | AC | 14.060 |
| | 0110- 1- 1 | CLEARING & GRUBBING (43317145201) | LS | 1.000 |
| | 0110- 2- 2 | SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN | AC | 1.000 |
| | 0120- 1- | REGULAR EXCAVATION | CY | 2,343.000 |
| | 0120- 4- | SUBSOIL EXCAVATION | CY | 2,687.000 |
| | 0120- 6- | EMBANKMENT | CY | 4,115.000 |
| | 0160- 4- | TYPE B STABILIZATION | SY | 17,200.000 |
| | 0285-701- | OPTIONAL BASE, BASE GROUP 01 | SY | 12,046.000 |
| | 0286- 1- | TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS | SY | 1,135.000 |
| | 0334- 1- 12 | SUPERPAVE ASPHALTIC CONC, TRAFFIC B | TN | 1,022.800 |
| | 0430-175-142 | PIPE CULVERT, OPT MATERIAL, ROUND, 42"S/CD | LF | 57.000 |
| | 0430-982-140 | MITERED END SECTION, OPTIONAL ROUND, 42" CD | EA | 6.000 |
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 149.000 |
| | 0527- 2- | DETECTABLE WARNINGS | SF | 200.000 |
| | 0550- 10-410 | FENCING, WOOD FENCE, 0.0-5.0' | LF | 4,776.000 |
| | 0570- 1- 1 | PERFORMANCE TURF | SY | 13,292.000 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 6,246.000 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (43317145201) | LS | 1.000 |
| Section 0003 Signing | | | | |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 26.000 |
| | 0700- 1- 13 | SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF | AS | 6.000 |
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 378.000 |
| | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK | LF | 138.000 |
| | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 18.000 |
| | 0711- 11-180 | THERMOPLASTIC, STANDARD, WHITE, YIELD LINE | LF | 135.000 |