

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	02220216	Call Order: 002	Proposal: E20L1	District:02
Counties:	DISTRICT-WIDE			
Road Name:	- BRIDGE-REPAIR/REHABILITATION			
Limits:	26040000			
Project(s):	43744215201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.312 Miles	Contract Days:	300	
Total Bridge Length:	0.376 Miles	Letting Date:	02/16/22	
Total Proposal Length:	0.688 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days (acq. time)	
Proposal Budget Estimate:	\$1,705,774.00			

Please read the full advertisement

**Description:**

(Various bridges over the Santa Fe & Suwannee rivers bridge numbers) Bridge pile jackets, shotcrete, and riprap installation on SR 20 (US 27) over Santa Fe River Bridge No. 260006 in Alachua County; bridge pile jackets and riprap installation on SR 136 over Suwannee River Bridge No. 290030 in Columbia County; shotcrete and riprap installation on SR 49 (US 129) over Santa Fe River Bridge No. 310005 in Gilchrist County; bridge pile jackets, steel repairs, and riprap installation on SR 47 over Santa Fe River Bridge No. 310007 in Gilchrist County; bridge pile jackets and bearing coating on SR 93 (I-75) over Suwannee River Bridge Nos. 370023 & 370030 in Suwannee County; and other incidental construction. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 002 Proposal: E20L1**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43744215201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43744215201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43744215201)	LS	1.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	75.000
	0401- 70-112	RESTORE SPALLED AREAS, SHOTCRETE, PROJECT 437442-1-52-01	CF	186.300
	0401- 70-113	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR - STYRENE-BUTADIENE, PROJECT 437442-1-52-01	CF	60.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	360.000
	0415- 10- 6	FIBER REINFORCED POLYMER BARS, #6 BAR	LF	8,715.000
	0457- 1- 22	STANDARD INTEGRAL PILE JACKET, STRUCTURAL, 16.1 to 30.0"	LF	43.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	942.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	32.000
	0460- 81-	RIVETS - HIGH STRENGTH BOLTS, REPLACEMENT	EA	12.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	5.700
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	413.300
	0530- 3- 8	RIPRAP- RUBBLE, REMOVE EXISTING AND REINSTALL	CY	50.700
	0530- 74-	BEDDING STONE	TN	151.800
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43744215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43744215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	880.000
	0102- 60-	WORK ZONE SIGN	ED	13,980.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,480.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	80.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	680.000
	0102-115-	TYPE III BARRICADE	ED	400.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	160.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	160.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	100.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,731.000
	0120- 5-	CHANNEL EXCAVATION	CY	271.600
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43744215201)	LS	1.000