

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	02220119	Call Order:	001	Proposal:	E20H3-R0	District:	02
Counties:	ALACHUA						
Road Name:	Gainesville Maintenance Routine Maint. Asphalt Repairs						
Limits:	Midpoint						
Project(s):	41021347233(*)	Federal Aid No:	N/A				
Total Roadway Length:	0.000 Miles	Contract Days:	365				
Total Bridge Length:	0.000 Miles	Letting Date:	01/19/22				
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10				
		Special Start Date:	N/A				
		Aquis/Flexible Start Time:	00 Days (acq. time).				
Proposal Budget Estimate:	\$500,000.00						

Please read the full advertisement

Description:

Milling and replacing failing asphalt in travel lanes on state-maintained roadways. RENEWAL OPTION. EXPERIENCE IN ASPHALT PAVING (FORM 850-070-01) MUST BE COMPLETED AND SUBMITTED WITH THE BID. BID EXPRESS MANDATORY.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E20H3-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)</b>				
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	1,500.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	21,000.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	4,000.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,500.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	160.000
	0425- 5-	MANHOLE, ADJUST	EA	3.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	1.000
	0660- 2-103	LOOP ASSEMBLY, F&I, TYPE C	AS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	4.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	50.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	25.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	50.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	7.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	4.000
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	25.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	4.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	50.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	50.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	50.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	7.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	7.000
	0711- 12-101	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	GM	4.000
	0711- 12-131	THERMOPLASTIC, REFURBISHMENT, WHITE, SKIP, 6"	GM	4.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	4.000
	0711- 12-231	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	GM	4.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	2,200.000