

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02220608	Call Order: 002	Proposal: E20W3	District:02
Counties:	DISTRICT-WIDE			
Road Name:	- BRIDGE-REPAIR/REHABILITATION			
Limits:	26040000			
Project(s):	43744215201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.312 Miles	Contract Days:	300	
Total Bridge Length:	0.376 Miles	Letting Date:	06/08/22	
Total Proposal Length:	0.688 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 Days (acq. time)	
Proposal Budget Estimate:	\$2,202,354.00			

Please read the full advertisement

Description:

(Various Bridges over the Santa Fe and Suwannee River Bridge Numbers) Bridge pile jackets, shotcrete, and riprap installation on SR 20 (US 27) over Santa Fe River Bridge No. 260006 in Alachua County; bridge pile jackets and riprap installation on SR 136 over Suwannee River Bridge No. 290030 in Columbia County; shotcrete and riprap installation on SR 49 (US 129) over Santa Fe River Bridge No. 310005 in Gilchrist County; bridge pile jackets, steel repairs, and riprap installation on SR 47 over Santa Fe River Bridge No. 310007 in Gilchrist County; bridge pile jackets and bearing coating on SR 93 (I-75) over Suwannee River Bridge Nos. 370023 & 370030 in Suwannee County; and other incidental construction. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 002 Proposal: E20W3

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43744215201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43744215201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (43744215201)	LS	1.000
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	86.500
	0401- 70-112	RESTORE SPALLED AREAS, SHOTCRETE, PROJECT 437442-1-52-01	CF	186.300
	0401- 70-113	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR - STYRENE-BUTADIENE, PROJECT 437442-1-52-01	CF	60.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	360.000
	0415- 10- 6	FIBER REINFORCED POLYMER BARS, #6 BAR	LF	8,715.000
	0457- 1- 22	STANDARD INTEGRAL PILE JACKET, STRUCTURAL, 16.1 to 30.0"	LF	43.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	942.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	32.000
	0460- 81-	RIVETS - HIGH STRENGTH BOLTS, REPLACEMENT	EA	12.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	5.700
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	413.300
	0530- 3- 8	RIPRAP- RUBBLE, REMOVE EXISTING AND REINSTALL	CY	50.700
	0530- 74-	BEDDING STONE	TN	151.800
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43744215201)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43744215201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43744215201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	880.000
	0102- 60-	WORK ZONE SIGN	ED	13,980.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	5,480.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	80.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	680.000
	0102-115-	TYPE III BARRICADE	ED	400.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	160.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	160.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	100.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,731.000
	0120- 5-	CHANNEL EXCAVATION	CY	271.600
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43744215201)	LS	1.000