



**Call Order: 003 Proposal: E20T7**

ALT	Item	Description	Unit	Quantity
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	199.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	1.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	5.000
	0107- 1-	LITTER REMOVAL	AC	3.130
	0107- 2-	MOWING	AC	1.820
	0110- 1- 1	CLEARING & GRUBBING (43089715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	287.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	368.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	30.400
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	30.400
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	2.000
	0425- 2- 72	MANHOLES, J-7, >10'	EA	1.000
	0425- 2- 91	MANHOLES, J-8, <10'	EA	1.000
	0425- 10-	YARD DRAIN	EA	2.000
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	8.000
	0430-175-115	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD	LF	41.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	7.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	125.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	47.000
	0430-175-242	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 42"S/C	LF	44.000
	0430-175-254	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 54"S/C	LF	62.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	8.100
	0430-880- 04	FLAP GATES, 49-60"	EA	1.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	45.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	284.000
	0570- 1- 1	PERFORMANCE TURF	SY	1,150.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43089715201)	LS	1.000
<b>Section 0003 Signing</b>				
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43089715201)	LS	1.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.011
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	86.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	60.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.008
<b>Section 0004 Lighting</b>				
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,546.000
	0715-540-000	LIGHT POLE COMPLETE- SPECIAL DESIGN, RELOCATE	EA	1.000
<b>Section 0005 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	304.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000

Call Order: 003 Proposal: E20T7

ALT	Item	Description	Unit	Quantity
<b>Section 0006 Architectural</b>				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	37.000
	0515- 20-100	PEDESTRIAN / BICYCLE RAILING, METAL STANCHIONS WITH CHAIN GUARD	EA	29.000
	0515- 20-101	PEDESTRIAN / BICYCLE RAILING, CONCRETE STANCHIONS AND CURB WITH CHAIN GUARD	LF	10.000
	0548- 52-	RETAINING WALL SYSTEM, SPECIAL DESIGN, CMU WALL WITH FOOTER, PROJECT 430897-1-52-01	SF	633.000
	0751- 11-101	ARCHITECTURAL- SPECIAL, FURNISH AND INSTALL (Timber Pergola Assembly)	LS	1.000