Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02231213 Call Order: 001 Proposal: E21D4 District:02

Counties: DIST/ST-WIDE

Road Name: Bridge Painting for Duval and Suwannee counties

Limits: Midpoint

Project(s): 41022137226(*) Federal Aid No: N/A

Project(s): 41022147216 Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	12/13/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	75 Days (acq. time)

Proposal Budget Estimate: $500,000.00

Please read the full advertisement

Description:

The work under this Site Specific, Contract consist of the complete paint removal via dry abrasive blast surface preparation to SSPC SP 10 standards and recoating of all structural steel and steel bearings on structure 720063. The work also consists of the complete paint removal via dry abrasive blast surface preparation to SSPC SP 10 standards and recoating of the steel bearings on structures 720276, 370024, 370031, and 720409.

Special Bid Requirement: The Contractor is required to have at least (3) years of Experience in Bridge Coating. The Contractor is required to be certified by The Society for Protective Coatings to the requirements of SSPC QP1 and/or SSPC QP2. For the Contractor to be responsive, SSPC QP1 and/or SSPC QP2 certifications must be submitted with the bid to the District Contract Administrator. Experience in Bridge Repair (Form 850-070-04) must be completed and submitted with the bid. LUMP SUM. BID EXPRESS MANDATORY.

Call Order: 001 Proposal: E21D4

ALT	Item	Description	Unit	Quantity
Section 0001 SUPERSTRUCTURE MAINTENANCE/REPAIR (MH)				
	E999- 10- 41	MAINTENANCE LUMP SUM CONTRACT	LS	1.000
	E999- 10- 41	MAINTENANCE LUMP SUM CONTRACT	LS	1.000