

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 02240117      Call Order: 001      Proposal: E21D3-R0      District:02  
Counties: DIST/ST-WIDE  
Road Name: Perform Routine Bridge Maintenance Repairs in District Two  
Limits: Midpoint  
Project(s): 41022137225      Federal Aid No: N/A  
Project(s): 41022147214(\*)      Federal Aid No: N/A  
Total Roadway Length: 0.000 Miles      Contract Days: 365  
Total Bridge Length: 0.000 Miles      Letting Date: 01/17/24  
Total Proposal Length: 0.000 Miles      Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time: 00 Days (acq. time)  
Proposal Budget Estimate: \$1,200,000.00

Please read the full advertisement

Description:

The work under this Work Document Driven Contract consists of providing labor, materials, equipment, and incidentals for Bridge Maintenance Repairs at bridge or other structure locations as specified by the Engineer in District 2. RENEWAL OPTION. EXPERIENCE IN BRIDGE REPAIR (FORM 850-070-04) MUST BE COMPLETED AND SUBMITTED WITH THE BID. BID EXPRESS MANDATORY.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E21D3-R0**

| ALT  | Item         | Description  | Unit | Quantity  |
|--|--------------|--|------|-----------|
| <b>Section 0001 SUBSTRUCTURE MAINTENANCE/REPAIR (MH)</b> |              |  |      |           |
|  | 0102- 14-    | TRAFFIC CONTROL OFFICER  | HR   | 730.000   |
|  | 0104- 10- 3  | SEDIMENT BARRIER   | LF   | 142.000   |
|  | 0104- 11-    | FLOATING TURBIDITY BARRIER   | LF   | 542.000   |
|  | 0110- 85-    | CLEANING INTERIOR OF SEGMENTAL BOX GIRDER SPAN   | EA   | 8.000     |
|  | 0121- 70- 2  | FLOWABLE FILL, MAINTENANCE CONTRACTS ONLY  | CY   | 37.000    |
|  | 0400-143-    | CLEANING & COATING CONCRETE SURFACE, CLASS 5   | SF   | 2,700.000 |
|  | 0400-145-    | CLEANING CONCRETE SURFACE  | SF   | 4,800.000 |
|  | 0400-153-    | NON SHRINK GROUT, F&I, MISCELLANEOUS- STRUCTURES REHAB   | CF   | 750.000   |
|  | 0401- 70- 6  | SPALLED AREAS RESTORE, THERMOSETTING POLYMER CONC  | CF   | 170.000   |
|  | 0411- 1-     | EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB   | GA   | 310.000   |
|  | 0411- 2-     | CRACKS INJECT & SEAL- STRUCTURES REHAB   | LF   | 574.000   |
|  | 0450- 83- 1  | BEAM REPAIR, STRAND SPLICES  | EA   | 14.000    |
|  | 0455- 76-    | WRAP PILE CLUSTERS   | EA   | 100.000   |
|  | 0458- 1- 21  | BRIDGE DECK EXPANSION JOINT, REHABILITATION, Poured JOINT WITH BACKER ROD                          | LF   | 5,710.000 |
|  | 0458- 1- 41  | BRIDGE DECK EXPANSION JOINT, HOT POUR  | LF   | 2,060.000 |
|  | 0470- 1-     | TREATED TIMBER, STRUCTURAL   | MB   | 8.000     |
|  | 0471- 1- 1   | FENDER SYSTEM,PLASTIC MARINE LUMBER,REINFORCED   | MB   | 4.000     |
|  | 0471- 1- 2   | FENDER SYSTEM,PLASTIC MARINE LUMBER, NON-REINFORCED  | MB   | 4.000     |
|  | 0506- 72-    | BRIDGE DRAINS- POWER CLEAN   | EA   | 121.000   |
|  | 0524- 2- 1   | CONCRETE SLOPE PAVEMENT, NON REINFORCED, 3"  | SY   | 600.000   |
|  | 0530- 1-100  | RIPRAP, SAND-CEMENT BAGS   | CY   | 50.000    |
|  | 0530- 3- 3   | RIPRAP- RUBBLE, BANK AND SHORE   | TN   | 29.000    |
|  | E102- 1- 3   | MAINTENANCE OF TRAFFIC (SITE SPECIFIC)   | LO   | 140.000   |
|  | E104- 1- 1   | SAND FILL FOR EROSION REPAIR   | CY   | 22.000    |
|  | E460- 19- 1  | ARMOR ANGLE (REMOVE)   | LF   | 400.000   |
|  | E460- 20- 1  | POLYMER JOINT REPLACEMENT  | CF   | 280.000   |
|  | E460- 20- 14 | ELASTOMERIC STRUCT JOINT SEAL REPLACE  | LF   | 8,996.000 |
|  | E470- 75-    | TIMBER FENDER SYSTEM REPAIR INCLUDES REMOVAL/DISPOSAL OF DAMAGED MATERIALS                         | LF   | 100.000   |
|  | E470- 75- 1  | FENDER SYSTEM FASTENING REPLACEMENT - GALVANIZED INCLUDES U-BOLT, CARRIAGE BOLTS AND COUPLING NUTS | EA   | 60.000    |