

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02240117	Call Order: 003	Proposal: E21L1-R0	District:02
Counties:	ALACHUA, DIST/ST-WIDE			
Road Name:	Gainesville Maintenance Concrete Repairs			
Limits:	Midpoint			
Project(s):	41021347259(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	01/17/24	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	00 Days (acq. time)	

Proposal Budget Estimate: \$275,000.00

Please read the full advertisement

Description:

The improvements under this work document driven contract consist of removal and replacement of concrete mitered end sections, sidewalks, driveways, curb and gutter, ditch pavement, ADA ramps, etc., as listed in the bid items within the state maintained right of ways in Alachua and Bradford Counties. Mobilization and Maintenance of Traffic are incidental to the pay items listed. RENEWAL OPTION. BID EXPRESS MANDATORY.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 003 Proposal: E21L1-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,210.000
	0120- 1-	REGULAR EXCAVATION	CY	25.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	25.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.000
	0425- 1-205	INLETS, CURB, TYPE 9, PARTIAL	EA	1.000
	0425- 1-209	INLETS, CURB, TYPE 9, MODIFY	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0425- 15- 41	INLET TOP, REPAIR, CURB INLET	EA	1.000
	0425- 15- 51	INLET TOP, REPLACE, CURB INLET	EA	1.000
	0430-991- 1	MITERED END SECT, REPLACE SLAB- MAINTENANCE USE ONLY	CY	20.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	15.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	15.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	15.000
	0520- 5- 41	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 4' WIDE	LF	10.000
	0520- 5- 42	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 6' WIDE	LF	10.000
	0520- 5- 46	TRAFFIC SEPARATOR CONCRETE- TYPE IV, 8.5' WIDE	LF	1.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,635.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	500.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	120.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	55.000
	0527- 2-	DETECTABLE WARNINGS	SF	20.000
	E425- 73- 3	FRAME AND GRATE (F&I)	EA	1.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	1.000
	E425- 73- 7	MANHOLE FRAME & COVER	EA	1.000
	E575- 1- 6	SODDING, BERMUDA	SY	450.000