

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

---

Letting:	02240605	Call Order: 001	Proposal: E21B3	District:02
Counties:	DUVAL			
Road Name:	REHABILITATE VARIOUS PEDESTRIAN OVERPASSES - BR-REP/REHAB			
Limits:	72090000			
Project(s):	43556225201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.012 Miles	Contract Days:	290	
Total Bridge Length:	0.191 Miles	Letting Date:	06/05/24	
Total Proposal Length:	0.203 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days (acq. time)	
Proposal Budget Estimate:	\$3,339,208.56			

Please read the full advertisement

**Description:**

(Rehabilitate Various Pedestrian Overpasses within Duval Co.) The improvements under this Contract consist of rehabilitation of various pedestrian bridges including temporary traffic signals, lighting, sidewalks, bridges – cleaning and painting, heat straightening, deck replacement, replace lateral bracing and gusset plates, remove and replace fencing and other incidental construction on SR 115, SR 10 and SR 9 in Duval County. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 001 Proposal: E21B3**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0400-145-	CLEANING CONCRETE SURFACE	SF	15,614.000
	0401- 70- 3	RESTORE SPALLED AREAS, LATEX MODIFIED MORTAR- ACRYLIC	CF	53.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	4.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	182.000
	0413-151-	METHACRYLATE MONOMER	GA	6.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	850.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	106.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	2,929.000
	0460- 95-	STRUCTURAL STEEL REPAIR	LB	4,066.000
	0507- 70-	ALUMINUM SIDEWALK FLOOR	SF	1,784.000
	0550- 10-938	FENCING, SPECIAL TYPE, 6.1-7.0', RESET EXISTING	LF	440.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43556215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43556215201)	LS	1.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43556215201)	LS	1.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (43556225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43556225201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (43556225201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	1,904.000
	0102- 60-	WORK ZONE SIGN	ED	11,260.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	13,531.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,160.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	327.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	716.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	290.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	290.000
	0102-115-	TYPE III BARRICADE	ED	991.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	112.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	112.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43556225201)	LS	1.000
<b>Section 0003 Signalization</b>				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	290.000