

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02240911	Call Order: 006	Proposal: E21P7-R0	District:02
Counties:	DIST/ST-WIDE, DUVAL			
Road Name:	Traffic Operations Contract			
Limits:	Midpoint			
Project(s):	41021677219(*)	Federal Aid No:	N/A	
Project(s):	41021687210	Federal Aid No:	N/A	
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	09/11/24	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14 Days (acq. time)	
Proposal Budget Estimate:	\$500,000.00			

Please read the full advertisement

Description:

The work under this Contract consists of Maintenance of traffic, installation / replacement of highway signing, installation / removal of thermoplastic or paint pavement markings, messages, and symbols, raised retro-reflective pavement markers, delineators, fence type B, highmast light pole removal, sign structure removal, etc. All work will be described in detail on individual work documents issued during the life of this contract. EXPERIENCE IN OVERHEAD SIGNS (FORM 850-070-03) MUST BE COMPLETED AND SUBMITTED WITH THE BID. EXPERIENCE IN PAVEMENT MARKINGS (FORM 850-070-06) MUST BE COMPLETED AND SUBMITTED WITH THE BID. EXPERIENCE IN SINGLE AND MUTLI POST SIGN REPAIR (FORM 850-070-08) MUST BE COMPLETED AND SUBMITTED WITH THE BID. RENEWAL OPTION. BUDGET ESTIMATE - \$500,000.00. BID EXPRESS MANDATORY.

Call Order: 006 Proposal: E21P7-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CONCRETE REPAIR (CY)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	90.000
	0102- 60-	WORK ZONE SIGN	ED	1,200.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	20.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	60.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	20.000
	0102-115-	TYPE III BARRICADE	ED	24.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	20.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	10.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	10.000
	0527- 2-	DETECTABLE WARNINGS	SF	500.000
	0550- 10-220	FENCING, TYPE B, 5.1-6.0', STANDARD	LF	1,000.000
	0550- 60-211	FENCE GATE, TYPE B, SINGLE, 0- 6.0' OPENING	EA	2.000
	0550- 60-212	FENCE GATE, TYPE B, SINGLE, 6.1 - 12.0' OPENING	EA	2.000
	0550- 60-213	FENCE GATE, TYPE B, SINGLE, 12.1-18.0' OPENING	EA	2.000
	0550- 60-214	FENCE GATE, TYPE B, SINGLE, 18.1-20.0' OPENING	EA	2.000
	0550- 60-222	FENCE GATE, TYPE B, DOUBLE, 6.1-12.0' OPENING	EA	2.000
	0550- 60-223	FENCE GATE, TYPE B, DOUBLE, 12.1-18.0' OPENING	EA	2.000
	0550- 60-224	FENCE GATE, TYPE B, DOUBLE, 18.1-20.0' OPENING	EA	2.000
	0550- 60-232	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 6.1-12' OPENING	EA	2.000
	0550- 60-233	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 12.1-18' OPENING	EA	2.000

Call Order: 006 Proposal: E21P7-R0

ALT	Item	Description	Unit	Quantity
	0550- 60-234	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 18.1-20.0' OPENING	EA	2.000
	0550- 60-235	FENCE GATE, TYPE B, SLIDING/CANTILEVER, 20.1-24' OPENING	EA	2.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	260.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	40.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	4.000
	0700- 1- 14	SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF	AS	2.000
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	AS	2.000
	0700- 1- 22	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013, 12-20 SF	AS	2.000
	0700- 1- 25	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/0700-013, 21-30 SF SHEETING AREA FOR BACK TO BACK SIGNS	AS	2.000
	0700- 1- 31	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, UP TO 12 SF	AS	2.000
	0700- 1- 32	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	AS	2.000
	0700- 1- 33	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, 21-30 SF	AS	2.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	10.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	70.000
	0700- 1-912	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-913	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I CANTILEVER GROUND MOUNT, 20.1-30.0 SF	EA	2.000
	0700- 2- 11	MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	2.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	2.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	2.000
	0700- 2- 17	MULTI- POST SIGN, F&I GROUND MOUNT, 201-300 SF	AS	2.000
	0700- 2- 18	MULTI- POST SIGN, F&I GROUND MOUNT, 301-400 SF	AS	2.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	2.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	2.000
	0700- 3-104	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 31-50 SF	EA	2.000
	0700- 3-105	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 51-100 SF	EA	2.000
	0700- 3-106	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 101-200 SF	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	2.000
	0700- 3-204	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 31-50 SF	EA	2.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	2.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	2.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	2.000

Call Order: 006 Proposal: E21P7-R0

ALT	Item	Description	Unit	Quantity
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	2.000
	0700- 3-402	SIGN PANEL, INSTALL, 12-20 SF	EA	2.000
	0700- 3-403	SIGN PANEL, INSTALL, 21-30 SF	EA	2.000
	0700- 3-404	SIGN PANEL, INSTALL, 31-50 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	4.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	2.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	2.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	2.000
	0700- 3-606	SIGN PANEL, REMOVE, 101-200 SF	EA	2.000
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	2.000
	0700- 4-621	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, SPAN	EA	2.000
	0700- 4-631	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, MONOTUBE	EA	2.000
	0700- 4-640	OVERHEAD STATIC SIGN STRUCTURE, REMOVE BRIDGE MOUNT	EA	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	20.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	30.000
	0700- 15- 2	IN-STREET SIGN ASSEMBLY, FURNISH AND INSTALL- FIXED BASE CONNECTION	EA	2.000
	0704- 1- 1	TUBULAR MARKER, DURABLE, 36" WHITE POST	EA	20.000
	0704- 1- 3	TUBULAR MARKER, 36" WHITE POST	EA	20.000
	0704- 1- 4	TUBULAR MARKER, 36" YELLOW POST	EA	20.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	12.000
	0705- 10- 2	OBJECT MARKER, TYPE 2	EA	4.000
	0705- 10- 4	OBJECT MARKER, TYPE 4	EA	4.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	30.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	150.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.400
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	12.000
	0710- 11-190	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ISLAND NOSE	SF	20.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	20.000
	0710- 11-331	PAINTED PAVEMENT MARKINGS, STANDARD, BLACK, SKIP, 6"	GM	0.400
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.800
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.400
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	8,000.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,000.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	400.000

Call Order: 006 Proposal: E21P7-R0

ALT	Item	Description	Unit	Quantity
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.000
	0711- 11-144	THERMOPLASTIC, STANDARD, WHITE, 2-2 DOTTED EXTENSION LINE, 12" FOR ROUNDABOUT	GM	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	24.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	100.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	200.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.600
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	200.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	300.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	2,000.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.400
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	4.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	4.000
	0711- 14-191	THERMOPLASTIC, PREFORMED, 6" WHITE, RAILROAD DYNAMIC ENVELOPE	LF	150.000
	0711- 14-193	THERMOPLASTIC, PREFORMED, 12" WHITE ON ASPHALT PAVEMENT RAILROAD DYNAMIC ENVELOPE	LF	70.000
	0711- 14-194	THERMOPLASTIC, PREFORMED, 12" WHITE WITH 4" OUTSIDE BLACK CONTRAST ON CONCRETE PAVEMENT, RAILROAD DYNAMIC ENVELOPE	LF	30.000
	0711- 14-241	THERMOPLASTIC, PREFORMED, YELLOW, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.400
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.200
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	4.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	6.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	2.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	500.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.200
	0713-103-121	PERMANENT TAPE, WHITE, SOLID W/CONTRAST, 6" PRIMARY LINE WIDTH, FOR CONCRETE SURFACES	GM	0.200
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.200
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	400.000
	0715- 19- 62	HIGH MAST LIGHT POLE, SHALLOW FOUNDATION REMOVAL	EA	4.000
	E102- 20-	PORTABLE LIGHTING UNIT (MAST MOUNTED)	ED	10.000
	E102- 74- 9	TRAFFIC CONES	ED	4,600.000
	E102- 97- 1	TRUCK MOUNTED ATTENUATOR (TEMPORARY)	ED	12.000
	E580-332- 21	TREE REMOVAL (4" TO 12")	EA	2.000
	E580-332- 22	TREE REMOVAL (13" TO 24")	EA	2.000
	E580-332- 23	TREE REMOVAL (25" TO 36")	EA	2.000
	E580-332- 24	TREE REMOVAL (37" TO 48")	EA	2.000

Call Order: 006 Proposal: E21P7-R0

ALT	Item	Description	Unit	Quantity
	E580-336- 4	PRUNING AND TRIMMING (TREES AND SHRUBS)	PM	0.600
	E700- 30- 1	SIGN PANEL OVERLAY, SINGLE POST	SF	20.000
	E700- 30- 2	SIGN PANEL OVERLAY, MULTI POST	SF	40.000
	E700- 30- 3	SIGN PANEL OVERLAY, OVERHEAD	SF	50.000
	E711- 3- 1	PAVEMENT MESSAGES (THERMOPLASTIC)	SF	200.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	5,600.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	400.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	7,000.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	3,000.000