

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	02250319	Call Order: 003	Proposal: E21M3	District:02
Counties:	LAFAYETTE			
Road Name:	SR51(HAL ADAMS BRIDGE) - BRIDGE-REPAIR/REHABILITATION			
Limits:	33040000			
Project(s):	43929225201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.130 Miles	Contract Days:	250	
Total Bridge Length:	0.130 Miles	Letting Date:	03/19/25	
Total Proposal Length:	0.260 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days (acq. time)	
Proposal Budget Estimate:	\$3,405,996.00			

Please read the full advertisement

Description:

(SR 51 (Hal Adams Bridge) over Suwannee River Bridge #330009) The Improvements under this Contract consist of Bridge steel repair, steel structural strengthening, expansion joint replacement, cracking repair, concrete beam strengthening, and other incidental construction on SR 51 (Hal Adams Bridge) Bridge No. 330009 over Suwannee River in Lafayette County. PREQUALIFICATION REQUIRED. BID EXPRESS MANDATORY.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 003 Proposal: E21M3

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	2.000
	0400-145-	CLEANING CONCRETE SURFACE	SF	160.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	5.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	250.000
	0413-151-	METHACRYLATE MONOMER	GA	19.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	1,740.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	207.000
	0450- 82-	BEAM REPAIR	LF	624.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, Poured JOINT WITH BACKER ROD	LF	183.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	71,856.000
	0460- 81-	RIVETS - HIGH STRENGTH BOLTS, REPLACEMENT	EA	390.000
	0461-114- 12	MULTIROTATIONAL BEARING ASSEM EXP, F&I, 251- 500KIPS	EA	4.000
	0561- 1-	COATING EXISTING STRUCTURAL STEEL (43929225201)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (43929225201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43929225201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	4,250.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	16,086.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	2,084.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	250.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,000.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43929225201)	LS	1.000
Section 0003 Signing				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	14.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.259
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.100