

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	02251119	Call Order: 002	Proposal: E21Q2-R0	District:02
Counties:	ALACHUA, BRADFORD, LEVY, DIXIE, GILCHRIST			
Road Name:	Gainesville Maintenance Drainage Repairs and Pipe Video Insp			
Limits:	Midpoint			
Project(s):	41021347273(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	365	
Total Bridge Length:	0.000 Miles	Letting Date:	11/19/25	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	00 Days (acq. time)	
Proposal Budget Estimate:	\$525,000.00			

Please read the full advertisement

Description:

The improvements under this work document driven contract consist of drainage system repairs and improvements to the existing drainage systems, inspections via video camera, cleaning and desilting storm sewer sections as directed by the Engineer in Alachua, Levy, Gilchrist, Dixie and Bradford Counties. Mobilization and Maintenance of Traffic are incidental to the pay items listed. RENEWAL OPTION. EXPERIENCE IN DRAINAGE REPAIR (FORM 850-070-05) MUST BE COMPLETED AND SUBMITTED WITH THE BID.

Call Order: 002 Proposal: E21Q2-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MANUAL) (TN)				
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	200.000
	0120- 1-	REGULAR EXCAVATION	CY	50.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	20.000
	0120- 3-	LATERAL DITCH EXCAVATION	CY	25.000
	0120- 6-	EMBANKMENT	CY	10.000
	0121- 70-	FLOWABLE FILL	CY	10.000
	0145- 1-	GEOSYNTHETIC REINFORCED SOIL SLOPE	SF	25.000
	0145- 71-	REINFORCEMENT GRID FOR SOIL STABILIZATION	SY	25.000
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	5.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0425- 15- 41	INLET TOP, REPAIR, CURB INLET	EA	2.000
	0425- 15- 42	INLET TOP, REPAIR, DITCH BOTTOM INLET	EA	1.000
	0425- 15- 51	INLET TOP, REPLACE, CURB INLET	EA	1.000
	0425- 15- 52	INLET TOP, REPLACE, DITCH BOTTOM INLET	EA	1.000
	0430- 94- 1	DESILTING PIPE, 0 - 24"	LF	400.000
	0430- 94- 2	DESILTING PIPE, 25 - 36"	LF	400.000
	0430- 94- 3	DESILTING PIPE, 37 - 48"	LF	300.000
	0430- 94- 4	DESILTING PIPE, 49 - 60"	LF	100.000
	0430- 94- 5	DESILTING PIPE, 61" OR GREATER	LF	100.000
	0430-174-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"SD	LF	16.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	60.000
	0430-174-130	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 30"SD	LF	24.000
	0430-174-136	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 36"SD	LF	24.000

Call Order: 002 Proposal: E21Q2-R0

ALT	Item	Description	Unit	Quantity
	0430-174-142	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 42"SD	LF	12.000
	0430-174-148	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 48"SD	LF	12.000
	0430-174-154	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 54"SD	LF	12.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	128.000
	0430-175-160	PIPE CULVERT, OPT MATERIAL, ROUND, 60"S/CD	LF	12.000
	0430-821- 23	CLEANING & SEALING EXISTING PIPE JOINT, 15" STORM SEWER	EA	20.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	25.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	25.000
	0430-821- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" STORM SEWER	EA	15.000
	0430-821- 38	CLEANING & SEALING EXISTING PIPE JOINT, 36" STORM SEWER	EA	15.000
	0430-821- 40	CLEANING & SEALING EXISTING PIPE JOINT, 42", STORM SEWER	EA	5.000
	0430-821- 41	CLEANING & SEALING EXISTING PIPE JOINT, 48", STORM SEWER	EA	5.000
	0430-821- 42	CLEANING & SEALING EXISTING PIPE JOINT, 54", STORM SEWER	EA	5.000
	0430-821- 43	CLEANING & SEALING EXISTING PIPE JOINT, 60", STORM SEWER	EA	1.000
	0430-821- 61	CLEANING & SEALING EXISTING PIPE JOINT, >60", STORM SEWER	EA	1.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	75.000
	0430-984-125	MITERED END SECTION, OPTIONAL ROUND, 18" SD	EA	4.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	4.000
	0430-984-133	MITERED END SECTION , OPTIONAL ROUND, 30" SD	EA	4.000
	0430-984-138	MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN	EA	4.000
	0430-984-140	MITERED END SECTION , OPTIONAL ROUND, 42" SD	EA	2.000
	0430-984-141	MITERED END SECTION , OPTIONAL ROUND, 48" SD	EA	1.000
	0430-984-142	MITERED END SECTION , OPTIONAL ROUND, 54" SD	EA	2.000
	0430-984-143	MITERED END SECTION , OPTIONAL ROUND, 60" SD	EA	2.000
	0430-991- 1	MITERED END SECT, REPLACE SLAB- MAINTENANCE USE ONLY	CY	20.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	10.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	10.000
	0524- 1- 4	CONCRETE DITCH PAVEMENT, NON REINFORCED, 6"	SY	900.000
	0524- 1- 49	CONCRETE DITCH PAVEMENT, 6", REINFORCED	SY	50.000
	0530- 1-100	RIPRAP, SAND-CEMENT BAGS	CY	10.000
	0906-173-200	TWO COMPONENT POLYURETHANE INJECTION	LB	800.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	30.000
	E425- 73- 2	REPAIR LEAKS IN MANHOLES AND INLETS	EA	20.000
	E425- 73- 3	FRAME AND GRATE (F&I)	EA	1.000
	E425- 73- 4	RESET EXISTING FRAME AND GRATE	EA	1.000
	E425- 73- 5	CLEANING MANHOLES AND INLETS (MANUAL)	EA	1.000
	E425- 73- 7	MANHOLE FRAME & COVER	EA	1.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	30,000.000
	E522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS- REMOVE AND REPLACE, 4"	SY	50.000
	E522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS- REMOVE AND REPLACE, 6"	SY	20.000
	E570- 2-	SEED & MULCH	SY	200.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	50.000
	E575- 1- 2	SODDING, CENTIPEDE	SY	50.000
	E575- 1- 4	SODDING, ST AUGUSTINE	SY	50.000

Call Order: 002 Proposal: E21Q2-R0

ALT	Item	Description	Unit	Quantity
	E575- 1- 6	SODDING, BERMUDA	SY	250.000