

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	02251119	Call Order: 001	Proposal: E2X45	District:02
Counties:	DUVAL			
Road Name:	SRA1A HUGUENOT PARK - GEORGE RIVER BR - BIKE PATH/TRAIL			
Limits:	72260000			
Project(s):	43316415201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.573 Miles	Contract Days:	270	
Total Bridge Length:	0.000 Miles	Letting Date:	11/19/25	
Total Proposal Length:	0.573 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	15 Days (acq. time)	
Proposal Budget Estimate:	\$6,150,018.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, base work, shoulder treatment, drainage improvements, curb & gutters, lighting, highway signing, guardrail, sidewalk/bicycle path, sheet pile walls, concrete barriers, and other incidental construction on SR A1A (Heckscher Dr) in Duval County from Huguenot Memorial Park to George River Bridge.
PREQUALIFICATION REQUIRED.

Call Order: 001 Proposal: E2X45

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43316415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43316415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	5,419.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	2,658.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	1,197.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,025.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	5,052.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	143.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	568.000
	0102-115-	TYPE III BARRICADE	ED	207.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	38.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,865.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	89.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	804.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	12.000
	0107- 1-	LITTER REMOVAL	AC	95.330
	0107- 2-	MOWING	AC	47.830
	0110- 1- 1	CLEARING & GRUBBING (43316415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	439.000
	0120- 1-	REGULAR EXCAVATION	CY	2,332.000
	0120- 6-	EMBANKMENT	CY	1,122.000
	0160- 4-	TYPE B STABILIZATION	SY	7,373.000

Call Order: 001 Proposal: E2X45

ALT	Item	Description	Unit	Quantity
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	5,853.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	668.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	10,600.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	257.800
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	69.700
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	1,146.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	10.100
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	67.400
	0415- 10- 5	FIBER REINFORCED POLYMER BARS, #5 BAR	LF	5,765.000
	0425- 1-711	INLETS, GUTTER, TYPE V, <10'	EA	2.000
	0425- 2- 93	MANHOLES, J-8, PARTIAL	EA	1.000
	0425- 3- 63	JUNCTION BOXES, DRAINAGE, J-7, PARTIAL	EA	1.000
	0425- 5-	MANHOLE, ADJUST	EA	7.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	5.000
	0425- 6-	VALVE BOXES, ADJUST	EA	1.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	71.000
	0436- 1- 1	TRENCH DRAIN, STANDARD	LF	593.000
	0451- 70-	PREST SOIL ANCHORS	EA	37.000
	0451- 70- 1	PRESTRESSED SOIL ANCHOR, PERFORMANCE TEST	EA	4.000
	0451- 70- 2	PRESTRESSED SOIL ANCHOR, CREEP TEST	EA	3.000
	0455-133- 3	SHEET PILING STEEL, F&I PERMANENT	SF	13,129.000
	0460- 2- 1	STRUCT STEEL, CARBON (43316415201)	LS	1.000
	0515- 2-311	PEDESTRIAN/ BICYCLE RAILING, ALUMINUM ONLY, 42" TYPE 1	LF	372.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	160.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	681.000
	0521- 72-110	SHOULDER CONCRETE BARRIER, VARIABLE HEIGHT, 38" - 62", SPECIAL DESIGN	LF	2,559.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	280.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	43.000
	0527- 2-	DETECTABLE WARNINGS	SF	92.000
	0530- 3- 3	RIPRAP- RUBBLE, BANK AND SHORE	TN	1,273.000
	0530- 74-	BEDDING STONE	TN	374.100
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	219.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	210.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	612.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	2.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3,799.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	834.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.654
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.085

Call Order: 001 Proposal: E2X45

ALT	Item	Description	Unit	Quantity
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	68.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	22.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	12.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.607
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43316415201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	1.340
	0654- 2- 21	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSY- SINGLE DIRECTION	AS	2.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	10.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	2.000
	0700- 1-211	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER TOP-MOUNT, LESS THAN 12 SF	EA	8.000
	0700- 1-311	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I BARRIER SIDE-MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	10.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	2.000
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	8.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	213.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43316415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	286.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	168.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	67.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	12.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	234.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	1.124
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.104
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.086
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	3.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	14.000
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	50.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	1.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	303.000

Call Order: 001 Proposal: E2X45

ALT	Item	Description	Unit	Quantity
	0715- 61-721	LIGHT POLE COMPLETE, F&I, STD POLE STD FOUNDATION, WILDLIFE SENSITIVE LUMINAIRE, 20' MOUNTING HEIGHT, 10' ARM LENGTH	EA	1.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	1.000