Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	02260218	Call Order: 002	Proposal: E21R3-R0		District:02
Counties:	ST JOHNS				
Road Name:	Mill and Resurface Roadways in St Johns County				
Limits:	Midpoint				
Project(s):	41021477270(*)		Federal Aid No: N/A		
Total Roadway Length:		0.000 Miles		Contract Days:	365
Total Bridge Length:		0.000 Miles		Letting Date:	02/18/26
Total Proposal Length:		0.000 Miles		Contract Execution Days:	10
				Special Start Date:	N/A
				Aquis/Flexible Start Time:	00 Days (acq. time)
Proposal Budget Estimate:			$399,700.00		

Please read the full advertisement

Description:

The work under this Work Document driven contract consists of providing labor, materials, equipment, and incidentals to mill and resurface various roads in St. Johns County. RENEWAL OPTION.

Call Order: 002 Proposal: E21R3-R0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	8,000.000
	0327- 70- 10	MILLING EXISTING ASPHALT PAVEMENT, 5" AVG DEPTH	SY	7,000.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	4,000.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	136.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	250.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76 -22	TN	180.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	8.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	8.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.100
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	550.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	550.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	520.000
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	2.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	10.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	500.000
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.100
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	200.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	4,000.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	4,000.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	2,500.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	2,500.000