Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02260218 Call Order: 005 Proposal: E21Y0 District:02

Counties: COLUMBIA, HAMILTON

Road Name: FC-5 Maintenance Contract in Columbia & Hamilton Counties

Limits: 29170000

Project(s): 45564057201(*) Federal Aid No: N/A

Total Roadway Length:	144.802 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	02/18/26
Total Proposal Length:	144.802 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	00 Days (acq. time)

Proposal Budget Estimate: $2,870,632.00

Please read the full advertisement

Description:

The work under this site-specific, work document driven contract consists of milling and replacing open graded friction course (FC-5) on I-75 in Columbia & Hamilton County & on I-10 in Columbia County at specified areas as provided in the appendix of this contract. All milled areas shall meet the surface texture requirements described in section 327-3.1.1 of the current FDOT Standard Specifications for Road and Bridge Construction. Mobilization and Maintenance of Traffic are incidental to the pay items listed. EXPERIENCE IN ASPHALT PAVING (FORM 850-070-01) MUST BE COMPLETED AND SUBMITTED WITH THE BID. The budgetary estimate for this contract shall be $2,870,632.00 over the term of the contract. Award will be made at the Departments Budgetary Estimate.

Call Order: 005 Proposal: E21Y0

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	64,951.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	2,761.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,407.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.130
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	7.120
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.280
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	6.130
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	7.120
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.300