Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02260121 Call Order: 005 Proposal: E21V8-R0 District:02
Counties: DIST/ST-WIDE
Road Name: District Wide Sinkhole Repair
Limits: Midpoint
Project(s): 41021827266(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	01/21/26
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	00 Days (acq. time)

Proposal Budget Estimate: $500,000.00

Please read the full advertisement

Description:

The improvements under this work document driven Contract consists of providing all labor, materials, equipment, and incidentals necessary to perform Subsurface Pressure Grouting and Shallow Subsurface Polyurethane Injection. The Subsurface Pressure Grouting program is to improve the subsurface conditions by injecting cement grout to fill voids and densify the soils as noted in a Cement Grout Injection Plan to minimize the potential for future ground subsidence. The Shallow Subsurface Polyurethane Injection will be used at drainage structures, drainage pipes, box culverts, asphalt and concrete pavement areas, sidewalk areas and bridge approach slabs for the purpose of densification of subgrade, filling voids, sealing drainage structures and realignment of surfaces. EXPERIENCE IN SINKHOLE REMEDIATION AND STABILIZATION USING SUBGRADE PRESSURE GROUTING MUST BE COMPLETED AND SUBMITTED WITH THE BID. RENEWAL OPTION.

Call Order: 005 Proposal: E21V8-R0

ALT	Item	Description	Unit	Quantity
Section 0001 PRESSURE GROUTING (CF)				
	0173- 76-	GROUT PIPE INSTALLATION	LF	2,750.000
	0173- 77- 1	SUBSURFACE PRESSURE GROUTING, SAND CEMENT	CY	250.000
	0906-173-200	TWO COMPONENT POLYURETHANE INJECTION	LB	25,000.000