Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	02260121	Call Order: 007	Proposal: E21Y1-R0		District:02
Counties:	ALACHUA, BRADFORD				
Road Name:	Ditch Cleaning and repairs and shoulder repairs				
Limits:	Midpoint				
Project(s):	21430157202(*)	Federal Aid No: N/A			

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	01/21/26
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	00 Days (acq. time)

Proposal Budget Estimate: $200,000.00

Please read the full advertisement

Description:

The work under this work document driven contract consists of removal of sediment from ditch pavement, roadside ditch cleaning and reshaping, box culvert desilting, lateral and outfall ditch excavation and repairs, lateral and outfall ditch vegetation mowing and removal, repairing and or reworking unpaved shoulders and utility strips, sod and erosion mat installation along state maintained right of ways, including ponds and pits in Alachua and Bradford Counties. Mobilization and Maintenance of Traffic are incidental to the pay items listed. RENEWAL OPTION.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 007 Proposal: E21Y1-R0

ALT	Item	Description	Unit	Quantity
Section 0001 SODDING (SY)				
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	10.000
	0120- 1-	REGULAR EXCAVATION	CY	50.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	50.000
	0120- 3-	LATERAL DITCH EXCAVATION	CY	260.000
	0120- 6-	EMBANKMENT	CY	25.000
	0120- 9- 1	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH UP TO 15'	LF	500.000
	0120- 9- 2	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH 15-30'	LF	450.000
	0120- 9- 3	DITCH CLEARING OF LARGE VEGETATION, DITCH WIDTH GREATER THAN 30'	LF	400.000
	0120- 10- 21	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH UP TO 15'	LF	500.000
	0120- 10- 22	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH 15-30'	LF	450.000
	0120- 10- 23	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH GREATER THAN 30'	LF	400.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	200.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	10.000
	E111- 1- 1	DITCH AND CANAL, CLEANING, UP TO 15' WIDE	LF	7,000.000
	E111- 1- 2	DITCH AND CANAL, CLEANING, 15'-30' WIDE	LF	5,000.000
	E111- 1- 3	DITCH AND CANAL, CLEANING, GREATER THAN 30' WIDE	LF	3,500.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	50.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	50.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	50.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	45.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	20.000
	E570- 2-	SEED & MULCH	SY	40.000
	E570- 9- 1	WATER FOR GRASS & PLANTS	MG	10.000
	E575- 1- 6	SODDING, BERMUDA	SY	4,000.000
	E577- 70-	SHOULDER REWORK	SY	100.000
	E577- 70- 1	REWORKING SHOULDERS (SPOT REPAIRS)	SY	50.000
	E577- 70- 2	REWORKING UTILITY STRIPS	SY	4,000.000