Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 02260520 Call Order: 004 Proposal: E21Z9 District:02

Counties: ST JOHNS, PUTNAM

Road Name: FC-5 Repairs in St. Johns and Putnam Counties

Limits: 78020000

Project(s): 45564067201 Federal Aid No: N/A

Project(s): 45564077201(*) Federal Aid No: N/A

Total Roadway Length:	29.170 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	05/20/26
Total Proposal Length:	29.170 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	00 Days (acq. time)

Proposal Budget Estimate: $6,217,751.00

Please read the full advertisement

Description:

The work under this site-specific, work document driven contract consists of milling and replacing open graded friction course (FC-5) on I-95 and US 1 (SR 5) in St. Johns County and SR 20 in Putnam County at specified areas as provided in the appendix of this contract. All milled areas shall meet the surface texture requirements described in Section 327-3.1.1 of the current FDOT Standard Specifications for Road and Bridge Construction. Mobilization and Maintenance of Traffic are incidental to the pay items listed. EXPERIENCE IN ASPHALT PAVING (FORM 850-070-01) MUST BE COMPLETED AND SUBMITTED WITH THE BID. The budgetary estimate for this contract shall be $6,217,751.00, over the term of the contract. Award will be made at the Departments Budgetary Estimate.

Call Order: 004 Proposal: E21Z9

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	27,932.000
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	1,117.280
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	715.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	2.150
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	2.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	2.380
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.550
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.000